


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-9

History of original corner establishment:



4 1/2' POST IN GROUND MARKED T2N S21 ON NE, R38E S28 ON SE, S29 ON SW AND S20 ON NW.

STONE HAS TWO NOTCHES ON SOUTH AND FOUR NOTCHES ON EAST

- 8" FIR N29E 14LKS. MKD. T2N R38E S 21 BT
- 30" PINE S35E 20LKS. MKD. T2N R38E S28 BT
- 30" FIR S69W 34LKS. MKD. T2N R38E S29 BT
- 10" FIR N42W 20LKS. MKD. T2N R38E S20 BT

Description of corner evidence found:

- 36" PINE S35E 13.2' SCRIBES VISIBLE
- 18" FIR SNAG N42W 13.2' SCRIBING VISIBLE BUT TREE IS PILED IN SLASH PILE AND THE ROOT HOLE IS NOT VISIBLE.


Description of monument and accessories | established to perpetuate the original location of this corner:

SET A 2"x30" IRON PIPE WITH A BRASS-CAP MARKED:

T2N	R38E
S20	S21
S29	S28
1978	
RLS 346	

- 10" FIR S46W 41.6' MKD. T2N R38E S29 BT
- 12" FIR N59W 42.2' MKD. T2N R38E S20 BT
- 16" FIR N58E 60.5' MKD. T2N R38E S21 BT

ALL BT'S HAVE A RED PAINTED STRIPE AND BT SIGNS. THE NEW BT'S HAVE A BRASS WASHER STAMPED RLS 346. THERE IS A 6' STEEL FENCE POST WITHIN 5' OF THE CORNER.



Office of.....COUNTY.....SURVEYOR..... County of.....UNION.....
 State of.....OREGON....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

..... by
 (COUNTY OFFICIAL) (DEPUTY)

UNION COUNTY SURVEYOR	
Date Received	_____
Date Filed	_____
By	_____
File No.	<u>221-83R</u>