


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner established with this survey.

H/J-15



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by proper subdivision of section from survey control...

Set a 2" x 30" aluminum pipe with 2½" aluminum cap 23" in ground & projecting 7" out of ground with surrounding earth mound & placed 6' steel fence post alongside with signs 54-2 & 54-9 attached. Cap marked as shown in corner diagram. No stones available for mound.

New bearing trees established:

Western larch 14" dia brs S31°W, 19.4' dist mkd C S S 1/64 S 10 BT.
Western larch 16" dia brs S19½°E, 56.7' dist mkd C S S 1/64 S 10 BT.

New bearing trees have a brass washer marked PLS 1639 nailed flush to face of blaze. Attached signs 54-3 & 54-9 & painted face of blaze & a 6' band of red around each bearing tree.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me & witnessed by F.S. Munro on October 02, 1989.

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON JULY 14, 1978 WILLIAM L. HANLEY 1639
--

Office of..... County Surveyor..... County of..... Union.....

State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by.....
(COUNTY OFFICIAL)

UNION COUNTY SURVEYOR
(DEPUTY)
Date Received <u>3-12-90</u>
Date Filed <u>3-12-90</u>
By <u>George L. Blackman</u>
File No. <u>12-90R</u>

*GPO-591-971, 1988

H/J-15