


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner established with this survey.

G-15



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position established by proper subdivision of section from survey control...

Set a 2" x 30" aluminum pipe with 2 1/2" aluminum cap 25" in ground & projecting 5" out of ground with surrounding earth mound & placed 6' steel fence post alongside with signs 54-2 & 54-9 attached. Cap marked as shown in corner diagram. No stones available for mound.

New bearing trees established:

Western larch 16" dia brs N25°E, 41.1' dist mkd C 1/4 S 10 BT.

Western larch 13" dia brs N79°E, 27.0' dist mkd C 1/4 S 10 BT.

New bearing trees have a brass washer marked PLS 1639 nailed flush to face of blaze. Attached signs 54-3 & 54-9 & painted face of blaze & a 6' band of red around each bearing tree.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me & witnessed by F.S. Munro on October 02, 1989.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

**OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639**

Office of..... County Surveyor..... County of..... Union
Oregon

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

UNION COUNTY SURVEYOR	
(DEPUTY)	
Date Received	<u>3-12-90</u>
Date Filed	<u>3-12-90</u>
By	<u>Wm T. Blaker</u>
File No.	<u>18-90 R</u>

*GPO-591-971, 1988

G-15