


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-12

History of original corner establishment:

No corner was originally set



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set pipe 22" in ground with mound of stone to cap.

Bearing Trees:

A Grand Fir 8" diam. bears N 68°W, 20.7 ft. scribed  
E 1/16 S9 BT

A Spruce 11" diam bears S77°E, 51.2 ft. scribed  
E 1/16 S16 BT

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped L'S 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red. Attached 54-2, 54-4 & 54-9 signs to metal post 3 ft. west of corner.

I hereby certify the above corner monument was established as herein described on September 14, 1981.

Witnesses: R. Orton  
G. Orton

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

OREGON  
SEPTEMBER 23, 1977  
HOWARD L. PERRY  
1984

Office of..... County Surveyor..... County of..... Union.....  
State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the...26... day of..... October..... 1981  
Howard L. Perry..... by.....  
(COUNTY OFFICIAL)..... (DEPUTY)


**UNION COUNTY  
SURVEYOR**

Date Received \_\_\_\_\_  
 Star OPO-700.276  
 Date Filed \_\_\_\_\_  
 By \_\_\_\_\_  
 File No. 336-84 R

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Refer to Union County Remonumentation Record No. 336-84R and Union County Survey No. 74-81 for original corner information and for 1981 establishment of corner position.



Description of corner evidence found:

Found the 1981 monument as previously described.

Refer to survey recorded during September, 1989 which revises Survey 74-81.

Description of monument and accessories established to perpetuate the original location of this corner:

Found and removed the monument established by Survey 74-81 and reset it at the revised position:

Reset a 2"x30" galvanized iron pipe, 26" in the ground, with brass cap marked:

(Note additional markings placed on brass cap)

|        |                  |
|--------|------------------|
| T2S    | R40E             |
| E 1/16 | $\frac{S9}{S16}$ |
|        | 1981             |
|        | Reset 1989       |
|        | OR PLS 1294      |

FROM WHICH:

The 1981 NW BT, an 8" Grand Fir, now an 8" Douglas Fir, alive and in good condition, marked as previously described, bears S 87° W 18.8 feet.

The 1981 SE BT, an 11" Spruce, alive and in good condition, marked as previously described, bears S 69° E 54.7 feet.

No new bearing BT's were marked. Note that the existing scribing on the SW BT does not reflect the section in which the tree now stands.

Magnetic compass (18-1/2° E. Declination). Steel Tape.

September 6, 1989

I hereby certify that the survey activities described on this record were performed under my direct supervision.

Gary L. Langlitz, LS 1099  
David Siderius



Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

|                              |                    |
|------------------------------|--------------------|
| <b>UNION COUNTY SURVEYOR</b> |                    |
| Date Received                | <u>9-18-89</u>     |
| Date Filed                   | <u>9-18-89</u>     |
| By                           | <u>G. LANGLITZ</u> |
| File No.                     | <u>170-89 R</u>    |