


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. F-24

History of original corner establishment:

None.



Description of corner evidence found:

None.

Corner falls on south slope at south edge of open area.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 10" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E: A 10" pine bears S55°E, 22.0 ft. scribed NE1/16 S12 BT. a 16" pine bears N65°W, 101.6 ft. scribed NE1/16S12 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' north and 54-2 on steel fence post 5' west of the corner.

T3S R34E  
NE 1/16  
+  
S12  
OR PLS 1051  
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland  
Harlan Eden

October 13, 1980

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Barry B. Barsour*

OREGON  
OCT. 17, 1975  
BARRY B. BARSOUR  
1051

Office of.....County Surveyor..... County of Union.....  
State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the 30th day of January....., 1981.

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

**UNION COUNTY  
SURVEYOR**

Date Received \_\_\_\_\_

★ GPO—798-276

Date Filed \_\_\_\_\_

By \_\_\_\_\_

File No. 382-84 R