


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-23

History of original corner establishment:

None.



Description of corner evidence found:

None.

Corner falls on steep NE slope in thick timber.

Description of monument and accessories I established to perpetuate the original location of this corner:

T3S R34E
 C1/4 + S12
 OR PLS 1051
 1980

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E: A 10" tamarac bears N77°E, 49.6 ft. scribed C1/4S12 BT. A 12" fir bears N16°W, 8.4 ft. scribed C1/4S12 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Palced 54-2 and 54-9 on steel fence post 5' north and 54-2 on steel fence post 5' east of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Doug Moser

October 17, 1980

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Barry B. Barbour

OREGON
 OCT. 17, 1975
 BARRY B. BARBOUR
 1051

Office of... County Surveyor..... County of... Union
 Oregon
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the... 30th day of... January....., 1981.

..... by
 (COUNTY OFFICIAL) (DEPUTY)

UNION COUNTY SURVEYOR

Date Received Nov 20 1980

Date Filed _____

By _____

File No. 384-84 R