


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-23

History of original corner establishment:

None.



Description of corner evidence found:

None.

Corner falls on NW corner of open rocky area.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked; Set pipe 10" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 21" pine bears N51°E, 86.8 ft. scribed CS1/16S12 BT.

A 16" pine bears N79°W, 102.8 ft. scribed CS1/16S12 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' east and 54-2 on steel fence post 3' south of the corner.

T3S R34E
 C
 S1/16 + S12
 C
 OR PLS 1051
 1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland

October 10, 1980

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

Barry B. Barbour

OREGON
 OCT. 17, 1975
BARRY B. BARBOUR
 1051

Office of...County..Surveyor..... County of..Union.....
 State of...Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the...30th day of...January....., 19..81

..... by
 (COUNTY OFFICIAL) (DEPUTY)

**UNION COUNTY
 SURVEYOR**

Date Received _____
 Date Filed _____
 By _____
 File No. 387-84 R

★ GPO—700-276