


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-24

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

T3S R34E
SE1/16
+
S12
OR PLS 1051
1980

At surbeyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 12" tamarac bears S75°E, 41.7 ft. scribed SE1/16S12 BT. A 16" pine bears S46°W, 41.0 ft. scribed SE1/16S12 BT. Painted balzes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped P1S 1051 on BTs. Palced 54-2 and 54-9 on steel fence post 5' north and 54-2 on steel fence post 5' west of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland

October 10, 1980

REGISTERED PROFESSIONAL LAND SURVEYOR
--

Barry B. Barbour

OREGON OCT. 17, 1975 BARRY B. BARBOUR 1051

Office of.....County Surveyor..... County of.....Union.....

State of.....Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 30th day of.....January....., 19.81

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

UNION COUNTY SURVEYOR
Date Received _____
★ OPC-788-278
Date Filed _____
By _____
File No. <u>388-84 R</u>