


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

-13-

History of original corner establishment: Corner established in 1873 by J. Hurlburt, under General Land Office Contract No. 201.


Surveyor General's records state:  
 Set Pine post 4 ft. long, 4 ins. square, 2 ft. in ground for cor. to Sec. 19-20-29-30.  
 Pine 30 ins. diam. S2<sup>0</sup>E 57 lks.  
 Pine 24 ins. dia. N27<sup>1</sup>/<sub>2</sub><sup>0</sup>E 296 lbs.  
 Balm 18 ins. dia. N55<sup>0</sup>W 77 lks.  
 Pine 30 ins. dia. S14<sup>0</sup>W 181 lks.

Index File No. R-5



Description of corner evidence found: Found no evidence of original corner post. Found live Pine 50" in dia. with visible scribing in open upper blaze for Northwest BT. Found live P. Pine 43" in dia. with visible scribing in open upper blaze for Southwest BT. Found dead P. Pine 36" in dia. with open blazes burnt so no scribing can be seen, Southeast BT.

Description of monument and accessories established to perpetuate the original location of this corner: Established a point at record bearing and dist. from each original BT and used the median to re-establish the original corner position.



Set 2<sup>1</sup>/<sub>2</sub>"x30" galvanized pipe with brass cap stamped:  
 Set pipe 22" in ground with mound of stone to cap.  
 From which:

Original BT's used:

A P. Pine 50" in dia. bears N27<sup>0</sup>30'E, 197.0 ft. with visible scribing in open upper blaze.

A P. Pine 43" in dia. bears S14<sup>0</sup>W, 122.2 ft. with visible scribing in open upper blaze.

A dead P. Pine 36" in dia. bears S 2<sup>0</sup>E, 39.1 ft. with open blazes replaced by a P. Pine 28" in dia. bears S40<sup>0</sup>E, 52.7 ft. scribed T3S R36E S29BT.

New BT a P. Pine 16" in dia. bears N38<sup>0</sup>W, 129.0 ft. scribed T3S R36E S19BT.

Attached 54-3 and 54-4 signs to all BT's. Attached brass washer stamped LS 1294 to foot blaze of new BT's. Painted blazes and 6" band around all BT's orange. Attached 54-2 sign to metal fence post 5' West of corner. Attached 54-2 and 54-4 signs to metal fence post 5' South of corner.

I hereby certify the above corner monument was re-established as herein described on October 4, 1979.

Witnesses: R. Orton  
 D. Allen

**REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR**

OREGON  
 SEPTEMBER 23, 1977  
**HOWARD L. PERRY**  
 1 2 9 4

Office of..... County Surveyor..... County of..... Union.....  
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19...79

..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

UNION COUNTY SURVEYOR	
Date Received	_____
Date Filed	_____
By	_____
File No.	448-84R