UNION COUNTY SURVEYOR

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T3S R40E H-17

S 11

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

NONE

No record of subsequent monumentation found in Union County survey records.

DESCRIPTION OF CORNER EVIDENCE FOUND:

NONE

See Survey No. 024-2001 DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

At position established by Survey No. 024-2001, I set a 2 ½" x 30" aluminum monument, marked as shown below, 28" in the ground, from which:

A 5/8" x 30" iron pin with 1 ½" aluminum cap bears N60°57'E, a distance of 6.35 feet, marked BGB SURVEY MARKER NE RP.

A 5/8" x 30" iron pin with 1 ½" aluminum cap bears S24°40'E, a distance of 21.59 feet, marked BGB SURVEY MARKER SE RP.

A 5/8" x 30" iron pin with 1 ½" aluminum cap in a North-South fenceline bears S27°53'W, a distance of 11.94 feet, marked BGB SURVEY MARKER SW RP.


A power pole #046109925 bears N77°W, a distance of 18.72 feet, to a 60d spike 1 ft. above ground.


I set a steel fence post 1 ft. North of monument.

I hereby certify that the corner was monumented on June 15, 2001. Witness: Norbert Volny and Gregory T. Blackman, Jr.

REGISTERED **PROFESSIONAL** LAND SURVEYOR OREGON G. ROBINSON RICK 2219

Renewal Date December 31, 2002





I used a Leica 530 GPS unit in the establishment of the new accessories. The Basis of Bearings is the same as that shown on Survey No. 024-2001. The distances are to the center of a 5/8"x30" iron pin with 1 ½" aluminum cap or as noted.