


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. R-8

History of original corner establishment:
Not set.



Description of corner evidence found:
None.

Corner falls near the Northwest corner of logged area and North of a fence corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2½" x 30" galvanized pipe with brass cap marked: Set pipe 24" in the ground, and placed about five rocks around.

T4N R4OE
E $\frac{S20}{S29}$ 1/16
OR PLS 1051
1978

No other rock in the area.

From which: A Tamarac 10" in dia. bears N13°W, 12.5 feet, scribed E1/16S20BT. A Tamarac 12" in dia. bears S40°E, 58.3 feet, scribed E1/16S29BT. Painted blazes red and 6" red band around. Placed 54-3s and 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot blazes. Placed 54-2 and 54-9 on steel fence post 4' East and 54-2 and 54-4 on steel fence post 5' North of corner. Placed 54-5 on tree 10' North of corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Dan T. Rowland

November 1, 1978

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Union.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the.....20 day of.....November....., 1978

..... by
(COUNTY OFFICIAL) (DEPUTY)

UNION COUNTY SURVEYOR

Date Received _____
Date Filed _____
By _____
File No. 62-83R