


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. S-8

History of original corner establishment:
Not set.



Description of corner evidence found:
None.

Corner falls in small patch of timber and East of small dry drain.

Description of monument and accessories established to perpetuate the original location of this corner:

T4N R40E
NE1/16 + S29
OR PLS 1051
1978

At surveyed point set 2 1/2" x 30" galvanized pipe with brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which: A Fir 16" in dia. bears N45° E, 47.3 feet, scribed NE1/16S29BT. A Fir 14" in dia. bears S43° E, 25.6 feet, scribed NE1/16S29BT. Painted blazes red and 6" red band around. Placed 54-3s and 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot blazes. Placed 54-2 and 54-4 on steel fence post 4' North and 54-2 and 54-9 on steel fence post 4' East of corner. Placed 54-5 on tree 5' West of corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Dan T. Rowland

November 1, 1978

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Union.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...20... day of...November... , 19...78

..... by
(COUNTY OFFICIAL) (DEPUTY)

UNION COUNTY
SURVEYOR

Date Received _____
Date Filed _____
By _____
File No. 72-83R