


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-7

**History of original corner establishment:**

This corner was originally set in error by PLS 1051 in 1978. This corner certificate is for the correct corner monument location which was established by PLS 1106 in 1987.



**Description of corner evidence found:**

A monument by PLS 1051 bears S85°36'E, 10.2' dist.

A 17" Western Larch brs N71°W, 19.7' dist scribed C $\frac{1}{4}$ S29 BT on a partially healed double blaze.

(This bearing tree, marked by LS 1051, was used as a reference to the new corner monument. Bearing and distance is to new corner).

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At correct corner location...

Set 2 $\frac{1}{2}$ " x 30" aluminum pipe with 2 $\frac{1}{2}$ " aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 12" Western Larch brs S22°E, 38.1' dist scribed C $\frac{1}{4}$ S29 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze & 6" red band around each BT. Set steel fence post West & South of corner, attached sign 54-9 to one post and 54-2 to both posts.

Compass declination 19° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards under my supervision on October 6, 1987.

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*William R. Wells*

OREGON JULY 22, 1987 WILLIAM R. WELLS 1106
---

Office of.....County Surveyor..... County of Union.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

(REFER TO SURVEY 1-88)


<b>UNION COUNTY SURVEYOR</b>
Date Received <u>1-11-88</u>
<small>GPO-791-311</small>
Date Filed <u>1-12-88</u>
By <u>G. LANGLITZ, DEPUTY</u>
File No. <u>48-88 R</u>

T-7

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. T-7

History of original corner establishment:  
Not set.



Description of corner evidence found:  
None.

Corner falls in N.E. corner of small wooded area near some large meadows.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe with brass cap marked: Set pipe 24" in the ground.

T4N R40E  
C1/4 + S29  
OR PLS 1051  
1978

No rock in the area.

From which: A Tamarac 16" in dia. bears N57°W, 10.4 feet, scribed C1/4S29BT. A Tamarac 15" in dia. bears S28°W, 12.5 feet, scribed C1/4S29BT. Painted blazes red and 6" red band around. Placed 54-3s and 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot blazes. Placed 54-4 and 54-9 on steel fence post 4' North of corner. Placed 54-5 on tree 8' South of corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David L. Landers  
Dan T. Rowland

October 24, 1978

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of... County Surveyor..... County of... Union.....  
State of... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the... 20... day of... November....., 1978

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

**UNION COUNTY SURVEYOR**

---

Date Received \_\_\_\_\_

Date Filed \_\_\_\_\_

By \_\_\_\_\_

File No. 84-83R