


CERTIFIED RECORD OF LAND CORNER MONUMENTATION 1

Index File No. U-4

History of original corner establishment:
Not set.



Description of corner evidence found:
None.

Corner on West slope about 300' East of Jarboe Creek.

Description of monument and accessories I established to perpetuate the original location of this corner:

T4N R40E
SE1/16 + S30
OR PLS 1051
1978

At surveyed point set 2½" x 30" galvanized pipe with brass cap marked: Set pipe 18" in the ground to bedrock and mound of stone around to cap.

From which: A Fir 14" in dia. bears N22°E, 15.7 feet, scribed SE1/16S30BT. A Fir 16" in dia. bears S46°E, 51.1 feet, scribed SE1/16S30BT. Painted blazes red and 6" red band around. Placed 54-3s and 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot blazes. Placed 54-2 and 54-4 on steel fence post 3' South and 54-2 and 54-9 on steel fence post 3' East of corner. Placed 54-5 on tree 15' South of corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Dan T. Rowland

November 1, 1978

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of... County Surveyor..... County of... Union.....

State of... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the... 20... day of... November....., 1978

..... by
(COUNTY OFFICIAL)

(DEPUTY)

RECORDED
INDEXED

NOV 1 1978

PLS 1051

95-83R