

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


INDEX FILE NO. N-25<sup>1</sup> (~~T4S R38E~~)

History of original corner establishment:

Original survey by T. Davenport, 1863, states:

Set post corner to Secs. 18, 19, 13 and 24.

Made mound of rock.



Description of corner evidence found:

None. Refer to survey filed concurrently with this record.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2"x30" Galvanized Iron Pipe, 6" in the ground to bedrock and supported in a mound of stone, 5 ft. base and 2 ft. high, with brass cap attached, marked:

From which:

An "+B0" chiseled on a horizontal bedrock surface (3'x10'x10' East of N-S fence) bears S7 1/2° E 42.5 ft.

Corner located 5 ft. east of N-S fence. Placed steel post with "ATTENTION" sign attached alongside monument.

Compass declination: 20° East.

T4S  
R38E R38E  
S13 | S18  
S24 | S19  
PLS1099  
1981

Witnesses: Gary Langlitz PLS 1099  
David Allen



Office of..... Surveyor..... County of..... Union.....  
State of..... Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the 29 day of OCTOBER, 1981  
Howard L. Perry..... by Gary Langlitz.....  
(COUNTY OFFICIAL) (DEPUTY)

**UNION COUNTY SURVEYOR**

Date Received 10-29-81

Date Filed 10-29-81

549-84R

File No. N-25 (T4S R38E)