


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No, B-8

History of original corner establishment:

None.



Description of corner evidence found:

Not Set.

Description of monument and accessories established to perpetuate the original location of this corner:

T9S R38E  
 NEL/16 + S5  
 OR PLS 1051  
 1980

At surveyed point set Crown Zellerbach 1" X 36" galvanized pipe and brass cap marked: Set pipe 12" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E: A 16" Fir bears S64°E, 69.6 ft, scribed NEL/16S5 BT. A 12" Pine bears S50°E, 24.7 ft, scribed NEL/16S5 BT, Painted blazes red and 6" red band around. Placed loc. tags, BT tags and property tags. Placed brass washers stamped PLS 1051 on BTs. Placed 54←4 on steel fence post 5' West of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland  
Robert Boling

June 9, 1980

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1975  
 BARRY B. BARBOUR  
 1051

Office of... County Surveyor..... County of... Union.....

State of... OREGON..... I hereby certify that the within instrument was filed in this office for record on the... 3<sup>rd</sup>... day of... July....., 1980

..... by ..... (COUNTY OFFICIAL) (DEPUTY)

**UNION COUNTY SURVEYOR**

Date Received \_\_\_\_\_

★ GPO-788-276

Date Filed \_\_\_\_\_

By \_\_\_\_\_

File No. 753-84R


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. B-8

**History of original corner establishment:**

Corner was set June 9, 1980, under contract for Crown Zellerbach. No original evidence for the 1/4 corner of sections 5 and 8 could be found and this corner was established by proportionate measurement between the original section corners.

Hanley Engineering had information on hand to restore this corner to it's original position and did so in March, 1981. The new position of this 1/4 corner, moved the interior corners and these were corrected in April, 1981.



**Description of corner evidence found:**

**Description of monument and accessories | established to perpetuate the original location of this corner:**

At new surveyed point set 1" X 36" galvanized pipe and brass cap set in 1980. Brass cap marked:  
Set pipe 12" in the ground to bedrock and mound of stone around to the cap.

T6S R38E  
NE1/16 + S5  
OR PLS 1051  
1980-1

From which by magnetic declination of N20°E:  
A 15" Fir bears S61°E, 67.2 ft. scribed NE 1/16 S5 BT.  
A 12" Pine bears S55°W, 26.4 ft. scribed NE 1/16 S5 BT. Corrected location tags and placed 54-4 on a steel fence post 7' West of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland  
Douglas Moser

April 9, 1981

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*  
OREGON  
OCT. 17, 1978  
BARRY B. BARBOUR  
1051

Office of..... County Surveyor..... County of..... Union.....  
State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 26 day of June....., 1981.  
Howard L. Perry..... by *Ray L. Laughlin*  
(COUNTY OFFICIAL) (DEPUTY)

**UNION COUNTY SURVEYOR**

Date Received 798.278

Date Filed \_\_\_\_\_

By \_\_\_\_\_

File No. 754-84R