

5-68

89-5

Ken Rogers  
907 G Ave.  
La Grande, Oregon

Feb. 6, 1968

center of section 34, T2S, R38EWM.

point of beginning of descriptions as exist in records

note;  $\frac{1}{4}$  distance recorded as 1320 feet.; found to be 1342.6 feet.

scale 1"=400'

existing 1/16 corner marker.

point of beginning for locating above parcels as now located on the ground. SE corner of  $NE\frac{1}{4}SW\frac{1}{4}$ .

#1 Beginning at the southeast corner of northeast quarter of southwest quarter of Section 34, T2S, R38EWM; thence west on south boundary of said  $NE\frac{1}{4}SW\frac{1}{4}$  594 feet; thence north parallel to east boundary of said  $NE\frac{1}{4}SW\frac{1}{4}$  586.8 feet; thence east 594 feet to east boundary  $NE\frac{1}{4}SW\frac{1}{4}$  said section; thence south to point of beginning.

#2 Beginning at a point which is on the east boundary of, and 586.8 feet from the southeast corner of northeast quarter of southwest quarter of Section 34, T2S, R38EWM. thence west parallel to south boundary of  $NE\frac{1}{4}SW\frac{1}{4}$  said section 594 feet; thence north parallel to east boundary of  $NE\frac{1}{4}SW\frac{1}{4}$  said section 223.5 feet; thence east 594 feet to east boundary of  $NE\frac{1}{4}SW\frac{1}{4}$  said section; thence south 223.5 feet to point of beginning.

#3. Beginning at a point, which is on the east boundary of, and 810.3 feet north of the southeast corner of the northeast quarter of the southwest quarter of Section 34, T2S, R38EWM; thence west parallel to the south boundary of the said northeast quarter of the southwest quarter of said Section 34, a distance of 594 feet; thence north parallel to the east boundary of the said northeast quarter of the of the southwest quarter of said Section 34; a distance of 532.3 feet, more or less, to the north boundary of the said northeast quarter of the southwest quarter of said Section 34; thence east on the north boundary of the said northeast quarter of the southwest quarter of said Section 34 to the northeast corner of the said northeast quarter of the southwest quarter of said Section 34; thence south 532.3 feet, more or less, to the point of beginning.

( note; these descriptions have a different point of beginning than the ones of record. The purpose is to make descriptions which fit the way in which the ground was surveyed out, and property lines as they now exist. )

25 38 34

594  
# 3 1100  
532.3

# 2 1101  
Rogers  
223.5

Kline  
# 1 1200  
594

REGISTERED  
J. M. ...

509.7  
22.6  
532.3

755.8  
733.2  
22.6