

Done Hardy J. Anderson.
Oregon, Oregon

Date: Aug 1976

ref. monument to section
cor on west side of road 31 feet
from corner. (to fence line of road)

Could not find any evidence of $\frac{1}{4}$ cor.

pipe
2-sec side

Anderson

Hardy

set $\frac{3}{8}$ " steel rod in fence line of
road and off set from sect on line.

78.76 ch.

2373.0 feet.

list by fld. notes: 80.11 ch.
list found by measurement from
intersection of fc. line on west
to center line of road on east
5363.0 feet.

The south $\frac{1}{4}$ corner of S 5, found.
Yellow pine bearing tree with
sapling visible (agrees with field notes)
Dist of south boundary of S 5, by field
note, is 80.76 ch.
Dist from S $\frac{1}{4}$ cor to intersection of fence
established as the section line to south
from the south east cor of sec 5 is 2373 ft.
measurement. From field notes this distance
is 2005.2 ft.

There is not any evidence of southeast
cor of section 5. There is an established
fence line running south for $\frac{1}{2}$ mile.
The $\frac{1}{4}$ cor between 8 and 9 was searched
for in 1965 by my records and could
not be found.

existing fence

scale 4" = 1 mile

James O'Leary

9 this cor. found
in 1965 and is
in center of N-S Co.
road. $\frac{3}{4}$ " pipe.

N 39
100