



① SECTION CORNER FOUND OLD STAKE ORANGE PAINTED ON ONE SIDE LEANING OVER WITH POINT 3\"/>

② 1/4 CORNER: NO MONUMENT FOUND. HELD E. OF HWY. ON LINE BETWEEN SECTION CORNERS. SET A TACK NAIL ON E. SET A 1/2\"/>

③ SECTION CORNER: FOUND A SLOPED TOPPED RED BASALT STONE 7\"/>

⑧ 1/4 CORNER: HELD A POINT MIDWAY BETWEEN R-O-W FENCES OF C.R. # 688 IN LINE WITH FENCES RUNNING EAST AND WEST. SET A 1 1/2\"/>

④ 1/4 CORNER: NO MONUMENT FOUND. HELD INTERSECTION OF FENCES RUNNING NORTH, SOUTH & EAST. SET A 7/8\"/>

⑭ G.L.O. "TOE OF HILL" TOPOGRAPHIC CALL WITH FENCE RUNNING EAST AT END OF LAKE

⑤ SECTION CORNER: NO MONUMENT FOUND. HELD A POINT IN A FENCE RUNNING SOUTH, 13 FEET SOUTH OF THE N.E. CORNER OF A TACK JACK. THIS POINT BEST FITS THE G.L.O. "TOE OF HILL" TOPOGRAPHIC CALL 20 CHAINS NORTH WHERE A FENCE RAN EAST IT ALSO BEST FITS INTERIOR FENCES AND ROADS AND IS 80 CHAINS SOUTH OF THE N.E. SECTION CORNER STAKE. NO MONUMENT SET.

⑦ SECTION CORNER: NO MONUMENT FOUND. HELD A POINT IN A FENCE RUNNING EAST ON LINE BETWEEN THE N.W. CORNER OF SECTION 7 AND THE S.W. CORNER OF SECTION 18. POINT IN FENCE NOT MONUMENTED AND IS 9.5' EAST OF A FENCE CORNER.

⑥ 1/4 CORNER: NO MONUMENT FOUND. HELD A POINT ON LINE BETWEEN SECTION CORNERS & THE E. OF HWY. SET A 3/4\"/>

⑨ SET A 1 1/2\"/>

⑩ SET A 1/4\"/>

⑪ SET A "I" SHAPED IRON 3/4\"/>

⑫ SET A 1/4\"/>

⑬ SECTION CORNER: FOUND A BUFF COLOR BASALT STONE, MASON CUT, 4\"/>

LAND SURVEY
IN
SECTION 7, T4S, R40E, W.M.
UNION COUNTY, OREGON
SCALE: 1" = 400' DATE: JULY 1971
TRUE BEARING BY STELLAR;
POLARIS & VEGA

() = DISTANCES BETWEEN FENCES.
o = MONUMENT SET AS NOTED.
--- = WIRE FENCE.
— = MEASURED LINES.
- - - = COMPUTED LINES.

REGISTERED
OREGON
LAND SURVEYOR
Harvey L. Barber
JULY 9, 1965
HARVEY L. BARBER
679

1471