

FOUND NORTH 1/4 COR. SEC. 22  
(See Vicinity Map)

T1S R39E  
1/4 S15  
S22  
1973  
PLS 848

RIM-ROCK AS PER G.L.O. NOTES

S15 S14  
S22 S23

Q DATA  
Δ = 14° 09' 00"  
R = 800'  
T = 99.29  
L = 197.57

Road P.I. S 2488.29 &  
E 146.01 From North  
1/4 Cor. Sec. 22

FOUND ROTTEN WOOD IN HOLE, SURROUNDED BY A MOUND OF STONE, WITH POST ALONGSIDE, (NO MARKS VISIBLE) AS CALLED IN THE ORIGINAL G.L.O. FIELD NOTES.  
SET 2-1/2" x 30" GALV. STEEL PIPE, WITH 3" BRASS CAP MARKED AS SHOWN & RAISED A MOUND OF STONE AROUND THE PIPE.

Aprox. Center 1/4 Cor. Sec. 22

Hay Shed  
Shed  
Grainery

Q DATA  
Δ = 5° 31' 35"  
R = 2600  
T = 125.49  
L = 250.78

BASIS OF BEARING  
BY SOLER OBSERVATIONS

HULL LANE

ROAD NO. 52  
N 0° 55' 06" W  
5261.75

FOUND REMAINS OF ROTTEN POST SURROUNDED BY A MOUND OF STONE, AS CALLED IN THE ORIGINAL G.L.O. FIELD NOTES.  
SET 2-1/2" x 30" GALV. STEEL PIPE, WITH 3" BRASS CAP MARKED AS SHOWN & RAISED A MOUND OF STONE AROUND THE PIPE.

(S 89° 30' W)  
S 89° 47' 58" W  
2624.73  
(39.90 Ch.)

FOUND SECTION CORNER OF RECORD, FOUND STAKE IN OLD MOUND OF STONE

S22 S23  
S27 S26

COUNTY ROAD NO. 52  
N 11° 32' 03" E  
675.25

2.7 Ac.

T1S R39E  
1/4 S22  
S27  
1973  
PLS 848

**VICINITY MAP**

EAST PORTION SECTION 22, T1S, R39E, W.M.  
Scale: 1" = 500'

**LEGEND**

- Set Monument at 1/4 Sec. Cor.
- ⊙ Found Section Corner of Record
- Found Unrecorded Monument
- Established Section Subdivisional Line (All other, broke lines are projected)
- Road Center Line, As it exists on the ground.
- Right of Way Line
- ( ) Indicates Bearing or Distance of Record

Q DATA  
Δ = 69° 10' 17"  
R = 80  
T = 55.16  
L = 96.6

MT. HARRIS ROAD  
N 52° 59' 43" E

Found Unrecorded, 1" Pipe, Set in A Mound of Stone, 6.6' West from Center of Section Line.

Aprox. South Center 1/16 Cor. Sec. 22

Road P.I., N 1349.44' &  
W 279.99 From South  
1/4 Cor. Sec. 22

Q DATA  
Δ = 13° 38' 38"  
R = 1200  
T = 143.55  
L = 285.76

REGISTERED PROFESSIONAL LAND SURVEYOR  
*Douglas M. Ferguson*  
OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

FOUND, SOUTH 1/4 COR. SEC. 22  
(See Vicinity Map)

**DETAIL MAP**

Scale 1" = 100'

**BAGETT-GRIFFITH-FERGUSON**  
LaGrande, Oregon  
Map of Survey  
ESTABLISHING RELATIONSHIP BETWEEN NORTH-SOUTH CENTER OF SECTION LINE & COUNTY ROAD, IN SEC. 22, T1S, R39E, W.M. UNION COUNTY, OREGON

SURVEYED FOR	Howard & Norma Feik	by D.M.F.
DESIGNED FOR		by
Scale: Variable	Drawn by D.M.F.	Sept. 1973

92-73