



NOTE: I find a fence corner with fences running North-South and East. These fences are a minimum of 50 to 60 years old as evidenced by ring count where they were attached to trees. I find no evidence of two original bearing trees at the corner. A blaze line follows these fences at about the time the area to the south was logged, approximately 15 years ago. I therefore accept these fences as the best available evidence of the position of the original 1/4 corner.

Fnd. 4" Fir Blazed 4 Sides

LEGEND

- Found Monument Of Record
- Set 5/8" x 30" Iron Pin With Plastic Cap Marked BGA Survey Marker
- * Existing Fence Line
- * Old Blaze Line
- () Record Bearing & Distance

REGISTERED PROFESSIONAL LAND SURVEYOR
Duane L. Griffith
 OREGON JULY 10, 1962
 DUANE L. GRIFFITH 644

BASIS OF BEARING
 Survey No. 38-76

ROAD
 END
 15
 22

Fnd. Bridge Spike and Bearing Tree

BAGETT, GRIFFITH & ASSOCIATES La Grande, Oregon		
Map of Survey Parcel In The S112 Of SE 1/4 Section 16 T1S, R 38E, WM		
UNION COUNTY, OREGON		
SURVEYED FOR	R. T. Opie	
SURVEYED BY	D. I. G.	10/76
Scale: 1" = 200'	Drawn by: d.a.d.	10/76