



BASIS OF BEARING
 ☿ BENTON STREET
 BEING EAST.

REFERENCE MATERIAL
 1922 CITY OF LA GRANDE
 REMONUMENTATION PLAT
 RECORD SURVEYS:
 23 - 77
 24 - 78

- LEGEND**
- CORNERS DESTROYED BY SEWER CONSTRUCTION, RE-ESTABLISHED FROM CITY OF LA GRANDE RECORD TIES.
 - ✚ CORNER POSITION BY INTERSECTION.
 - ▲ CORNERS ESTABLISHED AS NOTED.
 - SET 5/8" X 30" REBAR W/ CAPS.
 - () RECORD DATA BY CITY OF LA GRANDE REMONUMENTATION PLAT OF 1922.

NOTES

NO. 1 POINT ESTABLISHED BY GOING RECORD DISTANCE ON LINE FROM THE ☿ OF BENTON ST. & ☿ ALDER ST. TOWARDS THE ☿ OF BENTON ST. & ☿ WALNUT ST. AS PER RECORD SURVEY NO. 23 - 77.

NO. 2 POINT ESTABLISHED BY EXTENDING LINE FROM ☿ DIVISION ST. & ☿ WALNUT ST. TO ☿ BENTON ST. & ☿ WALNUT ST. SOUTH RECORD DISTANCE.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Barry B. Barbour
 OREGON
 OCT. 17, 1975
 BARRY B. BARBOUR
 1051

DEPENDENT RESURVEY OF LOTS 1-4 BLOCK 45, RIVERSIDE ADDITION TO LA GRANDE, UNION COUNTY, OREGON		
FOR: DEVERE CLARNEAU		
SCALE 1" = 60'	BARRY B. BARBOUR	1
DATE 4/78	LAND SURVEYOR	1