



BASIS OF BEARING

Solar Observation
 To the NW corner of section 16
 From WH-0
 August 10, 1978
 Latitude: 45° 18' 39"
 Declination: 15° 31' 48.4"
 Vertical Angle: 38° 33' 51"
 Mean Magnetic Declination: 20° East

SURVEYOR'S STATEMENT

I, Gregory T. Blackman, Registered Land Surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a correct representation of the survey I made during August and September, 1978, for the U.S. Forest Service, in accordance with the statutes of the State of Oregon and with the article of my contract.

Gregory T. Blackman
 PLS 991

WALLOWA - WHITMAN
 NATIONAL FOREST

LEGEND

- FOUND G.L.O. CORNER REMONUMENTED IN 1969 WITH BRASS CAP
- ⊙ FOUND G.L.O. CORNER, SET 2 1/2" x 30" IRON PIPE WITH BRASS CAP
- ⊙ SET 2 1/2" x 30" IRON PIPE WITH BRASS CAP
- A PROPORTIONATE DISTANCE
- P PRIVATELY OWNED LANDS
- () RECORD BEARING AND DISTANCE
- FOREST SERVICE BOUNDARY
- SET 2 1/2" x 30" IRON PIPE WITH BRASS CAP

NOTE
 For monumentation records, see monumentation sheets filed separately.

NOTE
 I found an approximate 5 chain error between the SE corner of section 16 and the E 1/4 corner of section 16. I have isolated the error to be north of the SE corner of section 16 from topographic calls to the south of said corner and on this basis I did not double proportion the SE corner of section 16. I did not find the marked stone at this corner, but a large mound of stone was very near (2 feet West and 7 feet North) a precomputed corner position using the SW corner of section 16, the E 1/4 corner of section 21, and the S 1/4 corner of section 15, and on the basis of best evidence I accepted the mound of stone. The stone is probably in the mound broken up or deteriorated from called size due to weathering.

FOREST SERVICE LANDS
 NE 1/4 Section 16
 NE 1/4 of the SE 1/4 of Section 16
 Section 15
 Section 14

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
Gregory T. Blackman
 OREGON

BAGETT, GRIFFITH & ASSOCIATES	
La Grande, Oregon	
Map of Survey	
SECTION 16 AND THE SOUTH LINES OF SECTION 14 AND 15 T 3 S R 35 E W.M.	
UNION COUNTY, OREGON	
SURVEYED FOR	Wallowa Whitman National Forest
SURVEYED BY	Gregory T. Blackman Aug. 1978
Scale 1" = 500'	Drawn by JJA & RGR Sept. 1978