



BASIS OF BEARING

SOLAR OBSERVATIONS, TAKEN AT THE
S E CORNER OF SECTION 24.
LATITUDE = 45°17'13"
MEAN VERTICAL ANGLE = 38° 52' 28"
MEAN SUN DECLINATION = 22° 48' 00"
MEAN HORIZONTAL ANGLE = 26° 48' 51"

MEAN MAGNETIC DECLINATION = 20° EAST

LEGEND

- Found monument of record.
- ⊙ Found evidence of G.L.O. corner, set 2-1/2" x 30" iron pipe, with brass cap
- Set 2-1/2" x 30" iron pipe, with brass cap, at proportionate distance
- (40ch) G.L.O. record bearing and distance.
- 402.337m Distance in meters
- Forest Service Boundary
- P Private owned land

REFERENCE MATERIAL

- G.L.O. notes
- B.L.M. remonumentation records
- Union County Surveyors records
- Forest Service corner records

SURVEYOR'S STATEMENT

I, Duane I. Griffith, registered land surveyor in the State of Oregon, hereby certify that this plat and the notes hereon or attached are a correct representation of the survey I made during July, 1979 for the U.S. Forest Service, in accordance with the statutes of the State of Oregon and with the articles of my contract.

Duane I. Griffith
O.P.L.S. 644

DESCRIPTION OF FOREST SERVICE LANDS

SECTION 24, T 3 S, R 33 E, W.M.
The W 1/2 of the NW 1/4; The SE 1/4 of the SW 1/4;
The W 1/2 of the SW 1/4; The NE 1/4 of the NE 1/4;
The S 1/2 of the SE 1/4;

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Duane I. Griffith
OREGON
JULY 10, 1968
DUANE I. GRIFFITH
644

NOTE

FOR MONUMENTATION RECORDS OF CORNERS
FOUND AND SET, SEE MONUMENTATION SHEETS
FILED SEPARATELY.

BAGETT, GRIFFITH & ASSOCIATES La Grande, Oregon Map of Survey		
FOREST SERVICE BOUNDARY Section 24 T 3 S, R 33 E, W.M. UNION COUNTY, OREGON		
SURVEYED FOR	Wallowa Whitman Nat'l Forest	
SURVEYED BY	d.i.g.	July 1979
Scale: 1" = 500'	Drawn by: d.i.g.	July 1979

57-79