



Basis of Bearing
 NORTH ALONG THE CENTER
 LINE OF N. GREENWOOD ST.

REFERENCE MATERIAL
 ORIGINAL PLAT OF CHAPLIN'S
 ADDITION TO THE CITY OF LA GRANDE.
 CITY SURVEY OF 1922

LEGEND

- ⊕ FOUND OR RE-ESTABLISHED MONUMENT AS SHOWN
- SET PK NAIL AT PROPORTIONATE DISTANCE
- SET 5/8" x 30" IRON ROD WITH PLASTIC CAP MARKED APA
- SET 1/2" IRON ROD AS REFERENCE
- SET PK NAIL IN POWER POLE AS REFERENCE

NARRATIVE OF SURVEY

This survey was performed to establish the boundaries of the North 84 feet of Lots 1 and 2, Block 151 of Chaplin's Addition to the City of La Grande.

The monument at the intersection of North Greenwood Street and Court Place was established at single proportionate distance between found monuments along the centerline of North Greenwood Street. The remaining controlling intersection monuments were found. The proportional size of the original lots was established after the record dimensions of the streets and alleys was deducted.

This survey was carefully performed using Theodolite, electronic distance-measuring equipment and steel tape.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
 SEPTEMBER 23, 1977
 HOWARD L. PERRY
 1294

NORTH 84' OF LOTS 1 & 2, BLOCK 151 OF CHAPLIN'S ADDITION TO THE CITY OF LA GRANDE		SHEET NO.	
LUNION COUNTY OREGON		1 / 1	
FOR: ANDERSON-PERRY & ASSOC		SCALE: 1" = 50'	
DATE: 1980		JOB NO. A	
 anderson perry & associates, inc. <small>engineering • surveying • materials testing</small> LA GRANDE, ORE. & WALLA WALLA, WASH.			