



LEGEND

- Found monument of record.
- Set 5/8" x 30" iron pin
- () Record bearing and distance
- ← Existing fence

REFERENCE MATERIAL

Oregon State Highway map 4B-26-11
 Map of Survey no. 30
 Map of Survey no. 31-72
 Deeds 149-523
 MF 71890
 MF 84784

BASIS OF BEARING
 SURVEY No. 31-72

SURVEYORS NARRATIVE

The survey consisted of locating a parcel in the NE 1/4 of the NW 1/4 of section 16 and separate a 2 acre parcel therefrom. I found no original G.L.O. corners on this section. The NE corner and the SE corner are accepted brass caps. The NW corner, the N 1/4 corner, the E 1/4 corner, and the center 1/4 corner are called on O.S.H. map no. 4B-26-11. I have double proportioned the SW corner in 1978 as shown on map of survey no. 111-78. In retracing O.S.H. map no. 4B-26-11, I have found the NE corner of section 16, Elgin east base, the SW corner and S 1/4 corner of section 17, and the P.I. at sta. 1030. I find the map to be acceptable for accuracy. Due to the harmonious fit with existing lines of occupancy I will use the positions shown on said O.S.H. map as the best available evidence for the position of the N 1/4 corner and the center 1/4 corner.

REGISTERED PROFESSIONAL LAND SURVEYOR

DUANE I. GRIFFITH
 OREGON
 JULY 10 1964
DUANE I. GRIFFITH
 644

BAGETT, GRIFFITH & ASSOCIATES

La Grande, Oregon

Map of Survey
 Parcels in the
 N.W. 1/4 of the NE 1/4 of
 Section 16, T 1 N, R 39 E, W.M.
 Elgin

UNION COUNTY, OREGON

SURVEYED FOR	ERNIE OKESON	
SURVEYED BY	d.i.g.	
Scale: 1" = 300'	Drawn by: d.i.g.	Mar. 1980

MAP OF SURVEY NO. 17-80