



LEGEND

- Found brass cap monument of record.
- Found evidence of G.L.O. corner set brass cap monument.
- Set brass cap monument at proportionate distance.
- () Record bearing and distance.
- 402.337m Distance in meters
- Forest Service Boundary.
- NF National Forest Lands.

NOTE:
For record of corners found and set, see monumentation sheets filed separately.

BASIS OF BEARING

Solar observations taken 900 ft. south of the NW corner of section 7
 Latitude = 45° 24' 43"
 Mean vertical angle = 14° 29' 45"
 Mean sun declination = -21° 10' 56"
 Mean horizontal angle = 294° 20' 47"
 Mean magnetic declination = 20° E

SURVEYORS STATEMENT

I, Duane I Griffith, registered land surveyor in the State of Oregon, hereby certify that this plat and the notes hereon or attached are a correct representation of the survey I made during April, 1980 for the US Forest Service, in accordance with the statutes of the State of Oregon and with the articles of my contract. I found no unusual conditions other than those shown.

Duane I Griffith
O.P.L.S. 644

DESCRIPTION OF FOREST SERVICE LANDS

Section 7, T 2 S, R 36 E, W.M.

- The SE 1/4
- The SW 1/4 of the NE 1/4
- The SE 1/4 of the NW 1/4
- The SE 1/4 of the SW 1/4

REFERENCE MATERIAL

- G.L.O. Notes
- B.L.M. Remonumentation records.
- Forest Service corner records.
- Union County Surveyor records;
survey no. 42-75
survey no. 43-75

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane I Griffith

OREGON
JULY 10, 1984
DUANE I. GRIFFITH
644

BAGETT, GRIFFITH & ASSOCIATES La Grande, Oregon		
Map of Survey FOREST SERVICE BOUNDARY Section 7 T 2 S, R 36 E, W.M. UNION COUNTY, OREGON		
SURVEYED FOR	Wallowa Whitman Nat'l Forest	
SURVEYED BY	dig. / gtb. / r.g.r.	4 / 1980
Scale: 1" = 600'	Drawn by: dig	5 / 1980