

Found marked stone, buried North and alongside brass cap.

From which:
 A 14" Pine bears S 44° E, 57.2 feet, marked 1/4 S12 BT
 A 12" Pine bears S 74° W, 12.4 feet, marked 1/4 S11 BT

From which:
 A 10" tamarack bears S 20° W, 10.6 feet, marked T3S R37E S14 BT
 A 12" tamarack bears N 44° W, 36.0 feet, marked T3S R37E S11 BT
 A 12" tamarack bears N 74° E, 60.2 feet, marked T3S R37E S12 BT
 No tree available in Section 13

No trees available
 Raised mound of stone

Found marked stone
 No trees available
 Raised mound of stone

From which:
 A 14" Pine bears S 34° W, 36.0 feet, marked C 1/4 S13 BT
 A 16" Pine bears N 18° W, 75.6 feet, marked C 1/4 S13 BT
 Raised mound of stone

From which:
 A 14" Pine bears S 58° W, 30.7 feet, marked 1/4 S24 BT
 A 12" Pine bears N 1° E, 47.5 feet, marked 1/4 S13 BT

From which:
 A 14" tamarack bears N 86° W, 30.6 feet, marked T3S R37E S13 BT
 A 16" Pine bears N 63° E, 48.5 feet, marked T3S R38E S18 BT
 A 16" Pine bears S 15° W, 8.5 feet, marked T3S R37E S24 BT
 No tree available in Section 19

BASIS OF BEARING

FORWARD BEARING AS PUBLISHED BY U.S.C. & G.S. FROM Δ COLLEGE TO Δ VALLEY

REFERENCE MATERIAL

ORIGINAL G.L.O. NOTES
 SURVEY NO. 16-77
 SURVEY NO. 1-78

LEGEND

- FOUND MONUMENT OF RECORD
- ⊙ SET 1 1/2" x 30" GALVANIZED IRON PIPE WITH BRASS CAP MARKED AS SHOWN
- (40 ch.) RECORD G.L.O. DISTANCE

NARRATIVE

This survey was done for Glenn Lester in preparation for a subdivision located in Section 13. I found evidence as indicated and established the remaining positions by standard proportionate measurement. I found no unusual conditions.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

OREGON
 JULY 13, 1973
 GREGORY T. BLACKMAN
 991

BAGETT, GRIFFITH & ASSOCIATES La Grande, Oregon		
Map of Survey		
BREAKDOWN OF SECTION 13 T3S, R37E, W.M. MORGAN LAKE UNION COUNTY, OREGON		
SURVEYED FOR	GLENN LESTER	
SURVEYED BY	GTB	7/80
Scale: 1" = 600'	Drawn by: RGR	7/80

53-80