



BASIS OF BEARING

Forward bearing as published by the U.S.C.
 & G.S. from Δ College to Δ Valley

REFERENCE MATERIAL

1922 Remonumentation of La Grande
 Original plat of Chaplin's Addition
 Survey number 19-68
 Survey number 90-71

LEGEND

- Found monument of record
- Found unrecorded monument
- Set 5/8" x 24" iron pin with plastic cap marked 'B-G-A SURVEY MARKER'
- () Record distance
- Centerline

NARRATIVE

This survey was ordered by Dean Harrison. Mr. Harrison is going to build on the lot and needed the four corners for setback purposes. I proportion the intersection in at Spruce and T from the found monuments at Spruce and S and Spruce and Jackson (West). I then established the position of Greenwood and T from survey number 90-71. I then have the block in position and proportion the lots in the usual manner. I find no unusual conditions on this survey.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Gregory T. Blackman

OREGON
 JULY 13, 1975
 GREGORY T. BLACKMAN
 991

BAGETT - GRIFFITH & ASSOCIATES La Grande, Oregon Map of Survey LOT 12, 13 AND THE EAST HALF OF LOT 14, BLOCK 152, CHAPLIN'S ADDITION LA GRANDE UNION COUNTY, OREGON		
SURVEYED FOR	DEAN HARRISON	
SURVEYED BY	GTB	10/80
Scale: 1" = 50'	Drawn by: RGR	10/80