



**LEGEND**

**FOUND MONUMENT AS DESCRIBED:**  
 SET 5/8" x 30" IRON ROD, BURIED APPROX. 12" IN ROADWAY UNLESS NOTED OTHERWISE.  
 ESTABLISHED BEARING TREES AS FOLLOWS: BEARINGS ARE TRUE, MEASURED BY STAFF COMPASS, COMPASS DECLINATION 20°E AND REFER FROM THE MONUMENT TO THE BT. DISTANCES WERE MEASURED HORIZONTALLY BY STEEL TAPE FROM THE MONUMENT TO A BRASS WASHER, MARKED "LS1294" NAILED TO THE LOWER BLAZE OF THE BT. ALL BT'S ARE SCRIBED "PI BT" ON A DOUBLE BLAZE. BT'S ALONG PORTION OF CENTERLINE DESCRIBED ON SURVEY NO. 75-72 ARE LOCATED WITH REFERENCE TO THE FOUND "REFERENCE MONUMENT" AND ARE SCRIBED "RP PI BT."

**CENTERLINE DATA**

STATION	BEARING	DISTANCE
1	S 62° 17' 41" W	272.29 FT.
2	S 81° 16' 03" W	195.01 FT.
3	S 50° 19' 05" W	261.46 FT.
4	S 30° 48' 20" W	270.04 FT.
5	S 87° 23' 22" W	74.54 FT.
6	N 49° 30' 54" W	116.28 FT.
7	N 86° 31' 07" W	311.06 FT.
8	S 51° 37' 51" W	96.37 FT.
9	S 18° 10' 57" W	315.03 FT.
10	S 44° 42' 32" W	158.59 FT.
11	S 61° 31' 42" W	313.47 FT.
12	S 75° 18' 40" W	117.06 FT.
13	N 72° 08' 24" W	215.82 FT.
14	N 61° 05' 12" W	51.07 FT.
15	N 44° 30' 39" E	51.47 FT.
16	N 69° 19' 31" E	245.97 FT.
17	N 30° 48' 05" E	166.06 FT.
18	N 4° 10' 13" W	254.74 FT.
19	N 27° 55' 25" E	323.61 FT.
20	N 3° 48' 54" W	322.15 FT.
21	N 2° 23' W	75.9 FT.
22	N 34° 44' E	134.7 FT.
23	N 84° 20' E	139.8 FT.
24	N 53° 09' E	289.5 FT.
25	N 10° 09' E	105.0 FT.
26	N 33° 29' E	248.5 FT.
27	N 6° 33' W	268.7 FT.
28	N 19° 05' W	164.1 FT.
29	N 5° 05' W	298.6 FT.
30	N 9° 13' W	394.7 FT.
31	N 49° 22' W	99.2 FT.
32	N 88° 01' W	113.0 FT.
33	S 67° 26' W	220.0 FT.
34	N 71° 36' W	100.0 FT.
35	N 38° 47' W	137.2 FT.
36	N 42° 43' E	189.6 FT.
37	N 45° 03' E	100.0 FT.
38	N 13° 58' E	542 FT. MORE OR LESS
39		

**NARRATIVE**

This survey was performed at the request of the Union County Court for purposes of locating and describing the centerline of Mt. Emily Road at its present location. Existing road records are ambiguous in their relationship to the present location of the roadway. Therefore, recent survey records and an actual field survey were utilized to locate and reference the existing centerline of Mt. Emily Road as depicted on this map.

Bearings and distances shown for that portion of the centerline located in Section 18 are taken directly from Survey No. 75-72 and utilize the basis of bearings shown thereon. Bearings of the centerline located in Section 19 are referenced to Survey 37-78.

**UNION COUNTY SURVEYOR**  
 Date Received 10-12-81  
 Date Filed 10-12-81  
 By G. Langhite, Deputy  
 File No. 63-81

**SURVEYOR'S CERTIFICATE**

I, Howard L. Perry, Union County Surveyor, in accordance with Oregon Revised Statutes Chap. 368, have surveyed and monumented the centerline of the existing Mt. Emily Road and I hereby certify that the attached map is a true and accurate representation of said survey.

September 1, 1981

*Howard L. Perry*  
 Howard L. Perry  
 Union County Surveyor

REGISTERED PROFESSIONAL LAND SURVEYOR  
 HOWARD L. PERRY  
 1294

MT. EMILY ROAD LOCATED IN SE 1/4, SEC. 18 AND NE 1/4 SEC. 19, T2S, R38E, W.M., UNION COUNTY, OREGON

FOR: UNION COUNTY COURT  
 SCALE: 1" = 200'  
 DATE: AUGUST, 1981  
 JOB NO. 686-10

**anderson perry & associates, inc.**  
 engineering - surveying - materials testing  
 LA GRANDE, ORE. & WALLA WALLA, WASH.

SHEET NO. 1/1