



SOLAR OBSERVATION
 Magnetic Variation 20°
 Date November 2, 1967
 Standard Time 9:02 A.M.
 G.C.T. 16:55
 Sun's Declination S 14°41.1'
 Refraction Correction -2.2
 Latitude 45°20'30"
 Sun's Altitude 20°42.3'
 Place Of Observation - S.E. Corner Of Section 36.

LEGEND
 * Found Monuments
 o Set Monuments With 4"x4"x48" Park Boundary Post
 I.P. 5/8"x30" Iron Pins
 W.C. Witness Corner

REGISTERED
OREGON
 LAND SURVEYOR
John E. Hollingsworth
 JULY 1, 1965
 John E. Hollingsworth
 691

UNION COUNTY SURVEYOR
 Date Received 2-16-82
 Date Filed 2-16-82
 By G. LANGRISH
 File No. 6-82

REFER TO NARRATIVE DRAWER 1/3
 2 S-36-5-36

OREGON STATE PARKS & RECREATION DIVISION
HILGARD JUNCTION STATE PARK
 UNION COUNTY
 SCALE: 1"=400' DATE: 8-28-69

RESTORED:

Set 5/8" x 30" iron pin 24" in ground.
Set 4" x 4" x 48" white post near pin scribed,
"T2S R36E S36 E1/4COR"
13" Pine N84 1/2°E 27.5 ft. scribed, "T2SR37ES31BTRS691"
Yellow corner tag on original BT.

Witnessed by: A. Slack
R. Hemmer
T. Stose

E - E - 1/64

ESTABLISHED:

Set 5/8" x 30" iron pin
Set 4" x 4" x 48" white post near pin.

Witnessed by: E. Haury
D. Shaw
T. Stose

SE - SE - 1/64

ESTABLISHED:

Set 5/8" x 30" iron pin
Set 4" x 4" x 48" white post
10" Pine S40 1/2°W 45.6 ft. scribed, "SESE 1/64 BTRS691"

Witnessed by: E. Haury
D. Shaw
T. Stose

C - N - SE - SE 1/256

ESTABLISHED:

Set 5/8" x 30" iron pin.
Set 4" x 4" x 48" white post near pin.
10" Pine S42°W 67.6 ft. scribed, "CNSESE 1/256 BTRS691"

Witnessed by: E. Haury
D. Shaw
T. Stose

WITNESS CORNER (304.59 ft. S89°27'E of C-N-SE-SE 1/256)

ESTABLISHED:

Set 5/8" x 30" iron pin near bank of Grande Ronde River
Set 4" x 4" x 48" white post near pin.
Erected mound of stone around pin.

Witnessed by: E. Haury
D. Shaw
T. Stose

UNION COUNTY SURVEYOR	
Date Received	_____
Date Filed	_____
By	_____
NARRATIVE DRAWING 1/3	
File No.	_____

REFER TO SURVEY 6-82

WITNESS CORNER (230.00 ft. NO° 37½° E of S-S 1/64 between sections 36 and 31)

ESTABLISHED:

Set 5/8" x 30" iron pin on gravel bar on the South side of the Grande Ronde River.

Set 3" x 84" iron post and paddle marked, "OREGON STATE PARK BOUNDARY do not disturb".

Erected mound of stone around pin.

Witnessed by: E. Haury
D. Shaw
T. Stose

S-S 1/64 BETWEEN 36 and 31

ESTABLISHED:

Set 5/8" x 30" iron pin.

Set 4" x 4" x 48" white post near pin.

Witnessed by: E. Haury
D. Shaw
T. Stose

REGISTERED
OREGON
LAND SURVEYOR

John E. Hollingsworth

JULY 9, 1965
John E. Hollingsworth
691

UNION COUNTY SURVEYOR	
Date Received	_____
Date Filed	_____
By	_____
NARRATIVE DRAWER 1/3	
File No.	_____

REFER TO SURVEY 6-32