



BASIS OF BEARING

SOLAR OBSERVATION TAKEN AT THE WEST 1/4 CORNER OF SECTION 27

REFERENCE MATERIAL

ORIGINAL G-L-O NOTES

LEGEND

- FOUND MONUMENT OF RECORD
- SET 2 1/2" x 30" ALUMINUM PIPE WITH ALUMINUM CAP
- ⊗ SET BRASS PLAQUE IN CONCRETE
- () RECORD BEARING AND DISTANCE
- *** FENCE LINE

NOTE: For corner information see remonumentation sheets filed separately.

NARRATIVE

This survey was ordered by Vince Naughton for Boise Cascade Corporation. I began my survey by tying the North 1/4 corner of section 16 and traversing Easterly to the Northeast corner of section 15. I also traversed South to the Southwest corner of section 15, and North to the brass cap at the Northwest corner of section 10. I searched for the West 1/4 corner of section 10 and the West 1/4 corner and North 1/4 corner of section 15 but found no evidence of the original corners. I therefore set the corner to sections 15, 16, 9 and 10 by double proportion methods. I then set the 1/4 corners to sections 9-10 and 10-15 by single proportionate measure. There was a tree of called species at the West 1/4 corner of section 10, at the approximate corner location that had been chopped open, if it was the original B.T. all of the scribe evidence had been destroyed, and I could not accept it as original evidence. After I set the corners shown, I blazed the property line along the North line of section 16 from the North 1/4 corner to the Northeast corner of section 16. I find no unusual problems with this survey.

UNION COUNTY SURVEYOR

Date Received 9-21-82

Date Filed 10-1-82

By G. LANGRISH DEPUTY

File No. 40-82

REGISTERED PROFESSIONAL LAND SURVEYOR

Gregory T. Blackman

OREGON

GREGORY T. BLACKMAN

991

BAGETT - GRIFFITH & ASSOCIATES

LaGrande, Oregon

Map of Survey

Section lines between sections 9, 10, 15, 16
T 1 N, R 38 E, W 1 M

UNION COUNTY, OREGON

SURVEYED FOR	BOISE CASCADE CORP.	
SURVEYED BY	GTB	9/82
Scale: 1"=1000'	Drawn by: ARC	9/82