
BASIS OF BEARING
 Solar observation taken at the North 1/4 corner
 of Section 15, T1N, R39E. (in Elgin Or.)

REFERENCE MATERIAL
 ORIGINAL GLO NOTES
 O.B. PAGE 196
 O.B. PAGE 200
 PLAT OF IMBLER ORCHARD TRACTS

LEGEND
 ● Found stone monument
 ⊙ Set monument as shown
 () Record distance

NOTE: For corner information see remonumentation sheets filed separately.


NARRATIVE

This survey was ordered by George Royes Jr. just for the purpose of remonumenting the corners shown. These corners were reset in 1889 by County Survey No. 93 in the old book of surveys on page 200, and by Imbler Orchard Tract. I located the West 1/4 corner of section 17, which was a well marked stone, which was called in the original plat of Imbler Orchard Tracts. The center of section, in my opinion was set by the survey on page 200 of the old book, however no record of a monument was recorded. Imbler Orchard Tracts indicated that the center of section was a stone. I therefore show the center of section as being set on Imbler Orchard Tracts. I found a stone 14" x 9" x 9" at the record distance on the true center of section line, at the

Northeast corner of Imbler Orchard Tracts. This stone has no record, however I am certain it marks the corner as the soil in the area is of loam and is free of stones to a depth of 3 to 4 feet. I also find fence posts set in concrete, within a foot or two of all the new monuments, which George Royes Jr., indicates his grandfather set to protect the corners. Mr. Royes' grandfather was P.E. Wade, and was one of the individuals that the aforementioned survey number 93 was performed for. This survey is not to locate property lines, it is only a pictorial record for the future to preserve the monuments.

UNION COUNTY
SURVEYOR
 Date Received 12-27-82
 Date Filed 12-28-82
 By G. LANGWITZ, DEPUTY
 File No. 53-82

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Gregory T. Blackman
 OREGON
 JULY 13, 1971
 GREGORY T. BLACKMAN
 991

 BAGETT - GRIFFITH & ASSOCIATES <small>LaGrande Oregon Map of Survey</small>		
BREAKDOWN OF SECTION 17, T1S R39E		
<small>UNION COUNTY, OREGON</small>		
SURVEYED FOR	GEORGE ROYES JR.	
SURVEYED BY	GTB	12-82
Scale: 1" = 600'	Drawn by: ARC	12-82