



### NARRATIVE

SURVEY WAS PERFORMED UNDER CONTRACT FOR THE OREGON DEPARTMENT OF FISH AND WILDLIFE. A WARRANTY DEED WAS ISSUED ON JUNE 17, 1980, BY BOISE CASCADE CORPORATION TO THE UNITED STATES OF AMERICA.

THE WARRANTY DEED WAS REFERRED TO BEARINGS AND DISTANCES BASED UPON A LOCAL GRID SYSTEM. THIS GRID SYSTEM WAS CONTROLLED IN 1979. AN ABSTRACT OF THIS CONTROL SYSTEM WAS OBTAINED AND USED FOR THIS SURVEY. FOUR POINTS THAT WERE WITHIN THE BOUNDARY WERE DESTROYED BY CONSTRUCTION. THE LOCAL GRID VALUES OF THE SECTION CORNER TO SECTIONS 13, 24, 18 AND 19, T3N, R39E. AND R40E. AND LGFH-13 WERE USED AS THE BASIS OF BEARING AND LOCAL COORDINATES.

CLOSED LOOP TRAVERSES WERE RUN TO CONTROL THE BOUNDARY. FROM THE CONTROL SURVEYS, THE BOUNDARY POINTS WERE SET BASED ON THE LOCAL GRID SYSTEM.

### MONUMENTATION

CORNER NUMBER 1 IS A 2 1/2" BRASS CAP ON AN 1/4" X 30" GALVANIZED PIPE SET 24" IN THE GROUND AND MOUND OF STONE AROUND TO CAP.

CAP IS MARKED: T3N R40E  
 LGFH #1  
 OR PL6 1051  
 1983

FROM WHICH: A 10" TAMARACK BEARS N 89 1/2° E, 27.5 FEET SCRIBED LGFH 1, BT.  
 A 8" FIR BEARS S 22 1/2° E, 27.5 FEET SCRIBED LGFH 1, BT.  
 PAINTED BLAZES RED AND 6" RED BAND AROUND. PLACED BEARING TREE TAGS.

CORNER NUMBER 16 IS A 2 1/2" BRASS CAP ON AN 1/4" X 30" GALVANIZED PIPE SET 22" IN THE GROUND

CAP IS MARKED: T3N R40E  
 LGFH #16  
 OR PL6 1051  
 1983

FROM WHICH: A 6" FIR BEARS S 20 1/2° W, 52.0 FEET, SCRIBED LGFH 16 BT.  
 A 10" FIR BEARS N 76° W, 36.5 FEET, SCRIBED LGFH 16 BT.

### BASIS OF BEARING

LOCAL GRID SYSTEM. FROM SECTION CORNER TO LGFH-13 BEING S 5° 12' 23" E, 576.13 FEET.

T.V. ANTENNA LOCATION: FROM CORNER #1 T.V. ANTENNA BEARS N 86° 09' 13" E, 1710.11 FEET. FROM CORNER #16 T.V. ANTENNA BEARS S 35° 45' 30" E, 2245.60 FEET.

### LEGEND

- FOUND RECORD BRASS CAP SECTION CORNER
- ▲ FOUND 2" IRON PIPE, FILLED WITH CONCRETE AND BRASS DISC STAMPED "LGFH 13 1979", CENTERED WITH A SCREW.
- SET 2 1/2" BRASS CAPS AS DESCRIBED.
- SET 5/8" X 30" REBAR AND MARKED CAPS.

I, BARRY B. BARBOUR, a registered surveyor in the State of Oregon, certify that this plat and the notes hereon, are a correct representation of a survey I performed during April 5 to April 7, 1983, for the Oregon Department of Fish and Wildlife in accordance with the articles of the contract and with the Statutes of the State of Oregon.

*Barry B. Barbour*  
 BARRY B. BARBOUR  
 Registered Land Surveyor  
 Oregon License 1051

UNION COUNTY  
 SURVEYOR  
 Date Received 4-20-83  
 Date Filed 4-21-83  
 By G. LAUGATE, Deputy  
 File No. 14-83

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*  
 OREGON  
 OCT 17 1975  
 BARRY B. BARBOUR  
 1051



LOOKINGGLASS FISH HATCHERY  
 SECTIONS 18 and 19, T3N, R40E, W.M.  
 UNION COUNTY, OREGON

OREGON DEPT. OF FISH AND WILDLIFE

SCALE 1" = 200'	BARRY B. BARBOUR PROFESSIONAL LAND SURVEYOR	SHEET NO. 1
DATE APRIL, 1983	P.O. BOX 833 BAKER, OREGON 97814	1