

### BASIS OF BEARING

Solar observation taken at the Southwest corner of Section 18, Township 4 South, Range 40 East, W.M.

### REFERENCE MATERIAL

Survey Number 72-77  
Survey Number 83-78  
Survey Number 112-78  
Survey Number 12-80

### Deed records

Volume 114 Page 6  
Volume 149 Page 402  
Volume 156 Page 129  
Microfilm No. 105776

### LEGEND

- Found monument as described
- Set 5/8" x 30" iron pin with plastic cap marked BGA SURVEY MARKER
- ( ) Record distance
- Centerline
- Existing fenceline

### NARRATIVE

This survey was done at the request of Frank Aldrich. The description of Mr. Aldrich's property states in part, "Commencing at a point 492 feet East of the Southwest corner of the Northwest quarter of Section 18". This corner falls on a manhole which was marked previously. The manhole has since been moved by road construction. I therefore use the record information of survey number 12-80, which tied the true position. I then placed the property as per deed calls. I made the North and South lines parallel with the centerline of Bryan Avenue and the East and West lines parallel with the West line of survey number 12-80.

### UNION COUNTY SURVEYOR

Date Received 5/23/83  
Date Filed 5-26-83  
By G. LANGLITZ, DEPUTY  
File No. 18-83

### REGISTERED PROFESSIONAL LAND SURVEYOR

*Handwritten Signature*  
OREGON  
JULY 10, 1954  
DUANE I. GRIFFITH  
644

**BAGETT - GRIFFITH & ASSOCIATES**  
La Grande, Oregon  
Map of Survey  
Parcels in the Southwest 1/4 of the Northwest 1/4 of Section 18, Township 4 South, Range 40 East of the Willamette Meridian  
Union  
UNION COUNTY, OREGON

SURVEYED FOR	Frank Aldrich
SURVEYED BY	d.i.g. 5/83
Scale: 1" = 20'	Drawn by: R.G.R. 5/83

