



**BASIS OF BEARING**  
 The forward bearing as published by the U.S.C. and G.S. from  $\Delta$  College to  $\Delta$  Valley - dated 1946

- REFERENCE MATERIAL**
- Old book of surveys - page 364
  - Survey number 18-66
  - Survey number 105-72
  - Survey number 56-73
  - Survey number 95-73
  - Survey number 24-75
  - Survey number 21-76
  - Survey number 25-84
  - Survey number 26-84
  - Unrecorded survey by J.R. Hagedorn for the O.S.H.D. dated July, 1971
- Deeds**
- Book W Page 163
  - Book 139 Page 506
  - Microfilm no. 33741
  - Microfilm no. 40270
  - Microfilm no. 55633
  - Microfilm no. 109738
  - Microfilm no. 47596

- LEGEND**
- Found monument as described
  - Found 5/8" iron pin with plastic cap set by survey number 25-84
  - Found 5/8" iron pin with plastic cap set by survey number 26-84
  - Set 5/8" x 30" iron pin with plastic cap marked BGA SURVEY MARKER
  - Existing fence line

**NARRATIVE**

This survey was ordered by Bill Anhorn of the Oregon State Highway Department. This survey is based entirely on survey number 26-84, which established a new boundary on the West line of the state owned property. It was decided after filing survey number 26-84 to extend the line running 4.79 feet East of and parallel to the original title line as shown. I extended the line South to a point on the extended North line of a 60 ft. wide parcel for access. I then jog back Westerly to the original title line, and then Southerly along the East end of the access parcel. This was necessary to maintain access to the state parcel.

NOTE: Fnd. 1" iron pin 18" below surface - North 3.43 ft. & 6.05 ft East of true corner. (See discussion survey no. 25-84)

REGISTERED PROFESSIONAL SURVEYOR  
 Date Received 9-23-84  
 Date Filed 9-25-84  
 G. LANGRISH, DEPUTY  
 File No. 35-84

REGISTERED PROFESSIONAL LAND SURVEYOR  
 Gregory T. Blackman  
 OREGON  
 GREGORY T. BLACKMAN  
 991

<b>BAGETT - GRIFFITH &amp; ASSOCIATES</b> La Grande, Oregon Map of Survey Parcel in the West half of the East half of Section 4, Township 3 South, Range 38 East of the Willamette Meridian La Grande UNION COUNTY, OREGON		
SURVEYED FOR	Oregon State Highway Department	
SURVEYED BY	G.T.B.	7/84
Scale: 1" = 100'	Drawn by: G.T.B.	7/84