



Solar Observation taken October 2, 1984 at a point 400 feet West of the S.E. corner of Section 27, T5S., R.38E., W.M.

LEGEND

- ⊕ Found Monument of Record set by OPLS 381 from original evidence. (1 1/2" Iron Pipe with Brass Cap)
- Found Monument of Record set by the B.L.M. from original evidence. (2 1/2" Aluminum Pipe with Aluminum Cap)
- △ Set a 2"x30" Galvanized Iron pipe with attached brass cap from original evidence.
- ⊙ Set a 2"x30" Aluminum Pipe with attached Aluminum Cap from original evidence.
- Set a 2"x30" Aluminum Pipe with attached Aluminum Cap at position determined by survey.
- () Record G.L.O. dimensions.

REFERENCE MATERIAL

Original G.L.O. survey notes by W.B. Barr, under Contract 388, dated May 7, 1881.

Union County Corner Restoration Record Numbers:

- 810-84R
- 811-84R
- 704-84R
- 705-84R

NOTE:

For more detailed corner information see remonumentation sheets filed separately.

NARRATIVE

This survey was ordered by Boise Cascade Corporation for the purpose of defining their ownership in the N 1/2 of N 1/2 of Section 27, T5S, R38E., W.M.

The section corners of this section were previously remonumented as shown from original evidence. The North 1/4 corner, East 1/4 corner and the South 1/4 corners were remonumented from original evidence during this survey. The West 1/4 corner was set at a proportionate position between the NW and SW section corners and the section was broken down as shown. Section subdivisional monuments were set at the positions shown.

UNION COUNTY SURVEYOR

Date Received 11-13-84

Date Filed 11-13-84

By G. LANGLITZ DEPUTY

File No. 48-84

REGISTERED PROFESSIONAL LAND SURVEYOR

Gary L. Langlitz

OREGON JULY 22, 1977

GARY L. LANGLITZ 1099

PROPERTY SURVEY IN SECTION 27, T5S., R.38E., W.M. UNION COUNTY, OREGON

FOR: BOISE CASCADE CORP., LAGRANDE, OREGON

SCALE: 1"=500'

DATE: SEP. OCT 1984

JOB NO. 884-20

Anderson Perry & Associates, Inc.
engineering • surveying • materials testing
LAGRANDE, ORE. & WALLA WALLA, WASH.

SHEET NO. 1/1