



LEGEND

- Found monument as described
- Centerline of easement
- - - Exterior line of easement

Centerline Curve Data

1 R=150.00' Δ=35°04'20" L=79.58' T=41.08' L.C.=78.34' N89°53'45" W	8 R=40.00' Δ=91°24'59" L=63.82' T=41.00' L.C.=57.26' N77°58'31" W	15 R=120.00' Δ=30°13'51" L=63.32' T=32.41' L.C.=62.58' N32°41'56" W
2 R=130.00' Δ=54°49'43" L=124.40' T=67.43' L.C.=119.71' N61°37'22" W	9 R=350.00' Δ=12°14'30" L=74.78' T=37.53' L.C.=74.64' N38°23'17" W	16 R=55.17' Δ=47°36'51" L=45.85' T=24.34' L.C.=44.54' N24°00'26" W
3 R=150.00' Δ=18°42'32" L=48.98' T=24.71' L.C.=48.76' N43°33'47" W	10 R=90.00' Δ=26°22'24" L=41.43' T=21.09' L.C.=41.06' N31°19'19" W	17 R=140.00' Δ=28°21'05" L=69.28' T=35.36' L.C.=68.57' N14°22'34" W
4 R=600.00' Δ=11°48'33" L=123.67' T=62.05' L.C.=123.45' N58°49'19" W	11 R=109.11' Δ=23°24'00" L=48.37' T=24.59' L.C.=47.97' N30°50'07" W	18 R=120.00' Δ=25°18'43" L=53.01' T=26.95' L.C.=52.58' N41°12'28" W
5 R=273.05' Δ=16°28'45" L=78.53' T=39.54' L.C.=78.28' N56°29'13" W	12 R=120.00' Δ=27°11'49" L=56.96' T=29.03' L.C.=56.43' N29°56'13" W	19 R=135.00' Δ=24°36'10" L=57.97' T=29.44' L.C.=57.52' N41°33'37" W
6 R=170.00' Δ=31°16'32" L=92.80' T=47.59' L.C.=91.65' N63°53'06" W	13 R=340.00' Δ=19°21'18" L=115.84' T=58.49' L.C.=115.28' N26°05'57" W	20 R=25.00' Δ=81°27'54" L=35.55' T=21.53' L.C.=32.63' N69°59'36" W
7 R=66.35' Δ=44°09'39" L=51.14' T=26.92' L.C.=49.88' S78°23'49" W	14 R=390.00' Δ=18°16'35" L=124.40' T=62.73' L.C.=123.88' N26°43'18" W	21 R=25.00' Δ=68°00'37" L=29.68' T=16.87' L.C.=27.96' N76°43'15" W

BASIS OF BEARING

Solar observation taken at a point 900 feet West of the East quarter corner of Section 18, Township 4 South, Range 41 East of the Willamette Meridian.



NARRATIVE

This survey was ordered by Bob Sheehy. Mr. Sheehy had constructed the irrigation ditch shown, and needed an exact location for a legal description. The ditch exists totally within Section 7, Township 4 South, Range 41 East of the Willamette Meridian, and is across Boise Cascade Corporation land. There were no monuments set on this survey. I am filing this location as a survey to provide a public record of the survey information this legal description was written from. The centerline shown is the actual location of the existing ditch. The easement is 5 feet wide on the Northerly side and 15 feet wide on the Southerly side of this centerline. The added width to the South is to provide enough width to include a service road constructed alongside of the ditch. The long tie from the intake to the government corner was necessitated by the lack of monumentation in this area. I find no other problems with this survey.

East 1/4 corner Section 18, T4S, R41E, W.M. Found 2" iron pipe with brass cap and accessories as per monumentation sheet 352-83R

REGISTERED PROFESSIONAL LAND SURVEYOR
Gregory T. Blackman
 OREGON
 GREGORY T. BLACKMAN
 391

BAGETT - GRIFFITH & ASSOCIATES La Grande, Oregon		
Location of water transmission easement situated in Section 7, Township 4 South, Range 41 East of the Willamette Meridian		
UNION COUNTY, OREGON		
SURVEYED FOR	Bob Sheehy	
SURVEYED BY	G. T. B.	11/84
Scale: 1" = 100'	Drawn by: R.G.R.	12/84