



BASIS OF BEARING

The forward bearing as published by the U.S.C. and G.S. from Δ College to Δ Valley, dated 1946

REFERENCE MATERIAL

Oregon State Highway drawing 6B-35-9
 Survey Number 37-71
 Survey Number 31-82
 Survey Number 31-83

Deed record microfilm numbers

76132	82167
80374	82169

LEGEND

- ▲ Found monument as described
- Found 5/8" iron pin with plastic cap set by survey number 31-83
- ⊙ Found aluminum monument set by survey number 31-83
- Section line
- - - Centerline
- Set 5/8" x 30" iron pin with plastic cap marked BGA SURVEY MARKER

NARRATIVE

This survey was ordered by Don Davidson. This survey is based on survey number 31-83, which established the Northwestern line of this parcel and also established the Southwesterly right of way line of highway 30, the section line between Sections 15 and 16, and the portion of Mr. Davidson's Southeasterly property line within Section 15. Mr. Davidson directed me to establish the Southeasterly line of this parcel 60 feet Northwesternly and parallel to his Southeasterly line. I placed the Southwesterly line of this parcel by extending the Southwesterly line of the parcel located by survey number 31-83 to the point 60 feet Northwesternly and parallel to Mr. Davidson's Southeasterly line as described above. I find no problems with this survey.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Gregory T. Blackman
 OREGON
 JULY 13, 1973
 GREGORY T. BLACKMAN
 991

UNION COUNTY
 SURVEYOR

Date Received 4-4-85
 Date Filed 4-17-85
 By G. LANGLITZ, DEPUTY
 File No. 9-85

BAGETT - GRIFFITH & ASSOCIATES La Grande, Oregon Map of Survey Parcel in the Northwest 1/4 of Section 15, and in the Northeast 1/4 of Section 16, Township 3 South, Range 38 East of the Willamette Meridian La Grande UNION COUNTY, OREGON		
SURVEYED FOR	Don Davidson	
SURVEYED BY	G. T. B.	4 / 85
Scale: 1" = 100'	Drawn by: R.G.R.	4 / 85