



LEGEND

- ① Found 1" iron pipe in fc. line, projects 6" from grnd.
- ② 5/8" rebar flush w/ground.
- ③ 5/8" rebar, bent 10" from end.
- ④ 5/8" rebar, bent 12" from end.
- ⑤ 5/8" rebar, bent 12" from end.
- ⑥ RR spike in wood tie.
- ⑦ RR spike in wood tie.
- ⑧ 5/8" rebar proj 8" above ground.
- Found monument as noted above.
- Set 5/8" x 30" rebar with plastic cap mkd. "HANLEY ENGR. PLS 1206".
- () Brg. and dist. of record Survey No. 44-71.

NARRATIVE

This survey for Eugene Chrisman was made for the purpose of marking on the ground, the parcel previously described as segregated from an existing larger parcel. Monuments shown on the Cecil Johnson Survey, No. 44-71, were recovered and the bearings and distances between monuments measured and compared with those of record. Most of the original monuments had extended about 12 inches above the ground and are now bent over. A 1-inch iron pipe now occupies the apparent position of the corner common to Secs. 14, 15, 22 and 23. I believe this replaces a fence post found during the Johnson survey, shown on that map of survey as the "approx. sec. cor. only". Origin is unknown. This survey accepts the positions of the found monuments although none of the measured distances are identical to those shown on map No. 44-71. Corner points were monumented according to the furnished description.

MAP OF SURVEY

A PARCEL IN THE NW 1/4 SEC. 23, T. 9 S., R. 39 E., W. M.
 Surveyed by Hanley Engrg.
 For Eugene Chrisman Jan.-Feb., 1985

SCALE 1" = 200'

UNION COUNTY SURVEYOR	
Date Received	5-6-85
Date Filed	5-10-85
By	G. LANGRISH DEPUTY
File No.	11-85

REGISTERED PROFESSIONAL LAND SURVEYOR
James D. Hanley
 OREGON
 SEPTEMBER 23, 1977
 JAMES D. HANLEY
 1206
 Baker, Oregon