

### BASIS OF BEARING

Solar observation taken at a point near the East 1/4 corner of Section 20, Township 1 South, Range 39 East of the Willamette Meridian

### REFERENCE MATERIAL

Survey Number 29-79  
Survey Number 41-79

### LEGEND

- Found 5/8" iron pin set by survey number 29-79
- Set 5/8" x 30" iron pin with plastic cap marked BGA SURVEY MARKER
- ( ) Record bearing and distance
- Found monument as described
- \*-x-\* Existing fenceline

### NARRATIVE

This survey was ordered by Dale Wagner on behalf of H.L. Wagner and Sons, Inc.. The Westerly line of this parcel lays on the Easterly right of way line of the railroad property. I located this line by projecting the right of way as established by survey number 29-79. The South line of this parcel was located by extending the North line of survey number 29-79. The remaining lines were established by boundary agreement. These corner locations were pointed out to me by the parties involved in the boundary agreement. I set the most Easterly pins 19 inches below the ground at their request as these pins fall in a cultivated field. I find no other problems with this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Gregory T. Blackman*

OREGON  
JULY 13 1973  
GREGORY T. BLACKMAN  
991

6-6-86

6-19-86

G. LANGUTZ, DEPUTY

20-86

BAGETT - GRIFFITH & ASSOCIATES  
La Grande, Oregon

Map of Survey  
Parcel in the Southeast quarter  
of Section 20, Township 1 South,  
Range 39 East, Willamette Meridian  
Imbler  
UNION COUNTY, OREGON

SURVEYED FOR	H.L. Wagner and Sons, Inc.	
SURVEYED BY	G. T. B.	6-86
Scale: 1" = 40'	Drawn by: R.G.R.	6-86

