REFERENCE MATERIAL UNION CO. SURVEY NO. 53-82

MICROFILM DOCUMENTNO. 40605 66292

UNION CO. REMONUMEN TATION RECORDS:

LEGEND

FOUND MONUMENT AS DESCRIBED ON UNION CO. SURVEY NO. 53-82 AND IN UNION CO. REMONUMENTATION RECORDS 108-84R AND 109-84R.

SET 5/0"X 30" IRON ROD (CONCRETE REINFORCING ROD) WITH YELLOW PLASTIC CAP ATTACHED, MARKED "APEA" PLACED STEEL FENCE POST ALONG SIDE.

FOUND 2" IRON PIPE WITH BRASS CAP,

BURIED 2'T.

MONUMENT 15 APPROXIMATELY 65' WEST OF THE & OF

THE EXTO CREEK-

This survey was performed at the request of Roy Hills for the purpose of establishing and describing a division line to be used in a future transaction involving property located in the South 1/2 of Section 7, T1S, R39E, W.M.

SURVEY NARRATIVE

-DIVISION LINE

N 89°49'27"W 3,650.45' (MONUMENT TO MONUMENT)

N55° 49'08"N 6338.271

MONUMENT IS APPROXIMATELY
15' EAST OF THE EXTG. FENCE

EXTG. FENCE AND CULTIVATION LINE

At Mr. Hills' direction, we established the division line shown hereon to run parallel with the existing Parks-Rhinehart County Road and to include 37 acres of land located South of the division line, West of the existing channel of Willow Creek and North and East of the existing fences and cultivation lines as shown. The "37 acres" is a land quantity determined by Mr. Hills. In addition to the establishment of this division line, legal descriptions were prepared and furnished to Mr. Hills for the properties located on either side of the division line.

It should be noted that this survey does not intend to provide a precise location of the original channel of Willow Creek which is mentioned in the deeds for properties in this area. Also, this survey should not be interpreted as defining the correct survey location of the centerline of Parks-Rhinehart Road or the Westerly line of Section 7, T1S, R39E.

UNION COUNTY SURVEYOR

Date Received 1-20-87

Date Filed 1-20-87 BY G. LANGLITZ DEPUTY

REFER TO NARRATINE DRAWER 1/9

REGISTERED **PROFESSIONAL** LAND SURVEYOR

EXTO. CHANNEL OF

WILLOW CREEK

OREGON GARY L. LANGLITZ 1099

A PROPERTY DIVISION LINE LOCATED IN THE SOUTH /2 OF SECTION 7, TOWNSHIP I SOUTH, RANGE 39 EAST, WILLAMETTE MERIDIAN, UNION COUNTY, OREGON FOR: ROY HILLS, RT.3 BOX 4430, ISLAND CITY, OR.

CENTER 1/4

SEC. 17

FOUND ALUMINUM PIPE WITH ALUMINUM CAP SET IN OPEN-TOPPED PIPE IN AN ASPHALT

ROADWAY .-

389°45'10"E 2668.00

1589°45'10E 2668.00

(BASIS OF BEARING)

SCALE. 1"=300'

DATE: DEC. 1986-JAN.1987 JOB NO 2701-50 LA GRANDE. ORE & WALLA WALLA. WASH.

SHEET NO.

## LEGAL DESCRIPTION

A parcel of land located in Section 7, Township 1 South, Range 39 East, Willamette Meridian, Union County, Oregon, said parcel being more particularly described as follows:

With reference to Survey No. 2-87 as recorded in the records of the Union County Surveyor.

That portion of the South one-half of Section 7 lying West of the original channel of Willow Creek and North of the "Division Line" as depicted on said Union County Survey No. 2-87, said "Division Line" being more particularly described as follows:

Beginning at a point in the center of the original channel of Willow Creek, thence N89°49'27"W to a 5/8" Iron Rod with yellow plastic cap marked "AP&A" which bears N24°10'09"W 3,890.75 feet from the 1/4 corner common to Sections 17 and 18, T.1S., R.39E., thence continuing N89°49'27"W, 3,650.45 feet to a 5/8" Iron Rod with yellow plastic cap marked "AP&A" which bears N55°49'08"W 6.338.27 feet from said 1/4 corner common to Sections 17 and 18, T.1S., R.39E., thence continuing N89°49'27"W to the Westerly line of Section 7 and the Point of Termination of said "Division Line",

EXCEPTING THEREFROM, any portion of that certain four (4) acres, more or less, in the South 1/2 of the Southeast 1/4 of Section 7, lying West of Willow Creek as presently located but East of the old channel of this creek and described in Union County Deed Records, Microfilm Document No. 66292, which may exist Northerly from said "Division Line" as described herein,

ALSO EXCEPTING THEREFROM, the following described parcel of land:

Commencing at a point on the South line of the County Road which is 567 feet East and 30 feet South of the Northwest corner of the Southwest quarter of Section 7, Township 1 South, Range 39 East of the Willamette Meridian; thence South 140 feet; thence East 115 feet; thence North 140 feet to the South line of said County Road; thence West 115 feet to the point of beginning.

SUBJECT TO, an easement for ingress and egress, said easement being more particularly described as follows:

A strip of land, the Westerly line of said strip of land being in common with the Westerly line of Section 7, T.1S., R.39E., said rip of land being 30.00 feet in width when measured Easterly at THE NO. LAKE THE LAKE In Filed 1-20-67 **5** right angle to said Westerly line of Section 7, said strip of And extending from the Southerly right-of-way line of Union County Road No. 135 (Parks-Rhinehart Road) Southerly to that certain "Division Line" as described herein and depicted on Union 1-20-87 Quality Survey No. 2-87,

SUBJECT TO easements and rights-of-way as the same may now exist or appear of record.

KEFER TO DURNEY Z-87

## LEGAL DESCRIPTION

A parcel of land located in Sections 7 and 18, Township 1 Range 39 East, Willamette Meridian, Union County, Oregon, said being more particularly described as follows: South, parcel

the Union County Surveyor. reference to Survey No. 2-87 25 recorded ij the records of

The Nort T.1S., R.39E; one-half of the Northwest one-quarter of, Section 18,

And that portion of the South one-half of Section the original channel of Willow Creek and South of the as depicted on said Union County Survey No. 2-87, said being more particularly described as follows: 1 7 lying West of "Division Line" d "Division Line"

Beginning at a point in the center of the original channel of Willow Creek, thence N89°49'27"W to a 5/8" Iron Rod with yellow plastic cap marked "AP&A" which bears N24°10'09"W 3,890.75 feet from the 1/4 corner common to Sections 17 and 18, T.1S., R.39E., thence continuing N89°49'27"W, 3,650.45 feet to a 5/8" Iron Rod with yellow plastic cap marked "AP&A" which bears N55°49'08"W 6,338.27 feet from said 1/4 corner common to Sections 17 and 18, T.1S., R.39E., thence continuing N89°49'27"W to the Westerly line of Section 7 and the Point of Termination of said "Division Line",

more or less, in the South 1/2 of the Southeast 1/4 of Section 7, lying West of Willow Creek as presently located but East of the old channel of this creek and described in Union County Deed Records, Microfilm Document No. 66292, which may exist Southerly from said "Division Line" as described herein,

being more TOGETHER WITH, an easement for more particularly described as ingress and egress, said easement
follows:

A strip of land, the Westerly line of said strip of land being in common with the Westerly line of Section 7, T.1S., R.39E., said strip of land being 30.00 feet in width when measured Easterly at a right angle to said Westerly line of Section 7, said strip of land extending from the Southerly right-of-way line of Union County Road No. 135 (Parks-Rhinehart Road) Southerly to that certain "Division Line" as described herein and depicted on Union tain "Division Line" as County Survey No. 2-87,

appear of record. UNION COUNTY SURVEYOR

9

SUBJECT TO easements

and rights-of-way as

the

same may now exist

RECER TO

G. LANGLITZ DEPUT