



BASIS OF BEARING

Solar observation taken at the Northeast corner of Section 21, Township 1 North, Range 39 East of the Willamette Meridian. (same basis as survey number III-78)

REFERENCE MATERIAL

Original GLO field notes
Survey Number III-78
Deed Volume 160 Page 427

LEGEND

- Found original GLO evidence and set a 2 1/2" x 30" aluminum monument
- Set 2 1/2" x 30" aluminum monument at position determined by survey
- () Record bearing and distance

NARRATIVE

This survey was done at the request of Lavon and Vera Culver. This survey is based on survey number III-78, which located the East line of Section 29 as shown. Survey number III-78 found two original bearing trees at the Southeast corner of Section 29, but did not monument the corner. I monument this corner with this survey. The Northeast corner of Section 29 is positioned by proportion as per survey number III-78 and I place the South 1/16 corner by standard proportionate method. I set steel fenceposts along the monumented line at approximately 200 ft. intervals at the request of Mr. and Mrs. Culver. The East line of the parcel the Culvers wanted to locate extends 660 feet South of the Southeast corner of Section 29. I did not monument this corner, as it would require breaking Section 32. I did however place steel fenceposts along the projection of the East line of Section 29 (S 0°16'04" E) for 660 feet, with the full understanding with the Culvers that this line was not a reflection of the true property line, but merely a projection. I find no unusual conditions with this survey.

UNION COUNTY SURVEYOR
Date Received 4-3-87
Date Filed 4-6-87
By G. LANGLITZ, Deputy
File No. 9-87

REGISTERED PROFESSIONAL LAND SURVEYOR
Gregory T. Blackman
OREGON
JULY 13 1973
GREGORY T. BLACKMAN
991

BAGETT - GRIFFITH & ASSOCIATES La Grande, Oregon		
Map of Survey		
Monumentation of the East line of the Southeast quarter of the Southeast quarter of Section 29, Township 1 North, Range 39 East of the Willamette Meridian		
UNION COUNTY, OREGON		
SURVEYED FOR	Lavon and Vera Culver	
SURVEYED BY	G.T.B.	4-87
Scale: 1" = 200'	Drawn by: R.G.R.	4-87