

line from this replacement for the BPA monument, to the I'

8-72 as shown. I find no other unusual conditions on this

iron pipe set by survey number 2-61. This is also harmonious with the 5/8" iron pin set by survey number

terminus of the South lines of survey numbers 1-70 and

10-75. The most Southeasterly monument of survey number 1-70 being an axle shaft that has been disturbed.

this line of the parcel. I then run Southeasterly along this alignment the call distance of survey number 10-75

I drive a line between these monuments for the alignment of

BASIS OF BEARING

The forward bearing as published by the U.S.C. and G.S. from Δ College to Δ Valley, dated 1946

REFERENCE MATERIAL

Union County monumentation records Survey number 26 Survey number 2-61 Survey number 1-70 Survey number 8-72 Survey number 10-75 Survey number 31-82

DEED RECORDS Volume D, Page 441 Volume D, Page 639 Volume D, Fage 639
Volume K, Page 489
Volume Q, Page 79
Volume IO4, Page 555
Volume IO4, Page 416
Volume I25, Page 481
Volume I45, Page 264 Microfilm number 40484

LEGEND

Found monument as described

Found monument in water valve box as per Union County monumentation records

Found unrecorded brass cap monument set by the Bonneville Power Administration

Set 5/8" x 30" iron pin with plastic cap marked BGA SURVEY MARKER

Record bearing and distance

Existing fenceline

Centerline

REGISTERED PROFUGGIORY. LAND SURVEYED Hugory T. Blockmon GREGORY T. BLACKMAN

UNION COUNTY SURVEYOR

Dath Received 8-31-87

Into Filed 9-14-87 3/G. LANGLITZ DEPUTY

File No. 23-87

AND BAGETT - GRIFFITH & ASSOCIATES La Grande, Oregon

Map of Survey

Parcel in the Northwest 1/4 of the Southwest 1/4 of Section 9, Township 3 South, Range 38 East of the Willamette Meridian

UNION COUNTY, OREGON SURVEYED FOR Bi-Mart 8-87 SURVEYED BY G,T,B, Drawn by: R.G.R. 8-87 **Scale:** j" = 100'