



BASIS OF BEARING

Solar observation taken at a point 1087 feet north and 1256 feet west of the southwest corner of section 31, Township 4 south, Range 41 east of the Willamette Meridian.

LEGEND

- Found aluminum monument set by survey no. 29-86.
- ⊙ Set 2 1/2" x 30" aluminum monument at position determined by survey.
- Found brass cap monument as per Union County monumentation records.
- Found aluminum monument set by survey no. 24-88.
- Blazed line
- () Record bearing, distance and acreage of Gesner GLO survey

NOTE:
For monumentation information, see monumentation sheets filed separately

REFERENCE MATERIAL

- Survey no. 29-86
- Survey no. 30-86
- Survey no. 24-88
- GLO contract number 683 by Alonzo Gesner, dated June 7, 1898.
- Union County monumentation records

NARRATIVE

This survey was done at the request of Mark Tsatsos. Mr. Tsatsos wanted the particular lines shown located preparatory to logging in this area. I base my location of the interior lines of this section on Union County Survey Number 24-88, which corrects the interior break of this section as shown on Union County Survey Numbers 29-86 and 30-86. I then break the South half of the section in the standard manner, considering the original GLO acreage calls as per the BLM manual. I then ran these lines from monument to monument, blazing the trees along these lines with 2 notches. I find no unusual conditions on this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR
Gregory I. Blackman
OREGON
GREGORY I. BLACKMAN
901

UNION COUNTY SURVEYOR
Date Received 9-9-88
Date Paid 9-15-88
By G. LANGRISH, DEPUTY
File No. 25-88

BAGETT - GRIFFITH & ASSOCIATES
LaGrande, Oregon
Map of Survey
Survey in the south 1/2 of section 31, Township 3 south, Range 41 east of the Willamette Meridian.
UNION COUNTY, OREGON
SURVEYED FOR Mark Tsatsos
SURVEYED BY gtb 7-88
Scale: 1" = 500' Drawn by: JPP 7-88