



5/4 Sec. 25, T45, R35E
Iron rock crib with stake
Iron property owner Wesley
B. Deive. stakes were set
by surveyor as 1/4 corner
some years ago. No record
in Union County Survey files

Projected 1/4 S centerline of Southwest quarter
parallel to East fence line along East line of
Section 36

SECTION 2

SECTION 1

SECTION 31

SECTION 36

SECTION 6

DETAIL "A"
1" = 200'

- denotes Brass Cap found as set by Greg Blackman in 1978
- denotes monument found as noted
- denotes 1/2 in. x 30 in. galv steel with 2 1/2 in. Brass Cap set
- denotes 3/8 in. x 30 in. iron pin with aluminum cap set
- () denotes original G.L.O. bearing and basis for bearings
- denotes property line

NARRATIVE

The purpose of this survey was to establish the boundaries of the Rita Clark property in Section 1, Township 4 South, Range 35 East and Section 36, Township 3 South, Range 35 East, W.M. The property involved is Lots 1, 2, and 3, and the southwest one-quarter of the northeast one-quarter of Section 1, and the southwest one-quarter of the southeast one-quarter and the south one-half of the of the southeast one-quarter of Section 36. We searched for the Northeast corner of Section 36, the Southeast corner of Section 36, the South one-quarter of Section 1, the Southeast corner of Section 36, the Northwest corner of Section 1, the East one-quarter of Section 1, the South one-quarter of Section 31, the East one-quarter of Section 36, and the West one-quarter of Section 36. None of these corners were found, having been destroyed by logging, farming, or movement of the Grande Ronde River.

We were able to find the corners shown and proportioned the corners as shown. There are several fences in the area but none of them fit anywhere near the section lines except the East line of Section 36, and the South line of Section 36. Boise Cascade has set cutting boundary markers along the South side of the Clark boundary but, according to their forester, they were set well inside the Clark boundary lines as they were not sure where the lines were.

Bearings are based upon the original G.L.O. bearing of the South line of Section 1.

Center one-quarter corner Bearing Trees
12" Pine bears 521°E 32.60'feet
12" Pine bears 517°W 37.70'feet

UNION COUNTY SURVEYOR	
Date Received	9-26-88
Date Filed	9-13-89
By	G. LANGRISH, DERM
File No.	34-88

Revised 7-31-89
added chain distances

David H. Klein

K KRUMBEIN ENGINEERING CO ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton Oregon	SCALE 1" = 200'
	DATE Oct 21, 1988
Survey for RITA CLARK	DRN. BY MK
located in NW/4, section 1, T45, R35E, W.M.	CKD BY DHK
	DRAWN BY SC, JSD