



BASIS OF BEARING

Bearings are based on found pipes at the NW corners of blocks 1 & 4. This bearing is recorded on the SUMMERVILLE CEMETERY PLAT.

REFERENCE MATERIAL

SUMMERVILLE CEMETERY PLAT.
Deed description, Bk 119, Page 247.

NARRATIVE

The Plat of the cemetery indicates that iron pins were set at block corners, I found 1-1/2" iron pipe at several corners. These fit very well with the record, and I accept them as the original monuments, set by Curfis. I found a stone 10" X 14" with a hole in the center, at the position called on the plat. The plat calls this stone the initial point and being the NE corner of the SW1/4 of the SW1/4 of section 18, T1S, R39E, W.M. I set a plastic survey cap with a magnet in the hole in the stone. I base the exterior lines of the cemetery parcel, on the description in the deed noted. I extended the existing fence line, on the east side, north to the intersection with the existing NE-SW fence line. I intersected this same fence line on the north line of the cemetery parcel.

LEGEND

- Found 1-1/2" iron pipe.
- Found stone 14" X 10", with a hole in the center, see narrative.
- Set 5/8" X 30" iron pin with plastic cap marked BGA SURVEY MARKER
- () Record bearing and distance
- Existing fence line.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane J. Griffith

OREGON
JULY 18, 1984
DUANE J. GRIFFITH
644

UNION COUNTY
SURVEYOR

Date Received 8-1-89

Date Filed 8-8-89

By G. LANGRISH, Deputy

File No. 12-89

BAGETT - GRIFFITH & ASSOCIATES LaGrande, Oregon		
Map of survey PARCEL IN THE SW 1/4 of Section 18 T 1 S, R 39 E, W.M. UNION COUNTY, OREGON		
SURVEYED FOR	SUMMERVILLE CEMETERY DISTRICT	
SURVEYED BY	d i g	July 1989
Scale: 1" = 50'	Drawn by: d i g	July 1989

SURVEY NO. 12-89