



BASIS OF BEARINGS

UNION COUNTY SURVEY NO. 74-81 (REFER TO SURVEY NARRATIVE)

LEGEND

- POSITION AS SHOWN ON UNION CO. SURVEY NO. 74-81 - NOT VISITED DURING THE COURSE OF THIS SURVEY REVISION.
- △ FOUND ALUMINUM CAP PROPERLY MARKED ON 2" ALUMINUM PIPE, ESTABLISHED IN 1988 FROM EVIDENCE OF THE ORIGINAL G.L.O. SURVEY BY WILLIAM HANLEY, PLS 1639 (REMONUMENTATION RECORD NO. 134-88.R)
- RESET EXISTING 2"x30" GALV. IRON PIPE WITH BRASS CAP TO REVISED POSITION AS SHOWN ON THIS DRAWING. ADDED THE MARKINGS "RESET 1989" TO BRASS CAP.
- SFNF SEARCHED FOR - NOT FOUND
- () G.L.O. RECORD DIMENSION

REFERENCE MATERIAL

- GENERAL LAND OFFICE SURVEY BY HENRY MELDRUM CONTRACT NO. 450, 1882
- UNION COUNTY SURVEYS 74-81 AND 35-88
- UNION COUNTY CORNER REMONUMENTATION RECORDS
 - 335-84 R
 - 336-84 R
 - 337-84 R
 - 338-84 R
 - 134-88 R

NOTE:

REFER TO THE REMONUMENTATION RECORDS FILED WITH THIS DRAWING FOR A COMPLETE DESCRIPTION OF THE REVISED CORNER MONUMENT AND ACCESSORIES.

SURVEY NARRATIVE

THIS SURVEY REVISES THE CORNER POSITIONS ESTABLISHED AS SHOWN ON UNION COUNTY SURVEY NO. 74-81, DUE TO THE RECENT RECOVERY OF THE ORIGINAL G.L.O. CORNER TO SECTIONS 3-4-9-10, T.2S., R. 40 E., BY WILLIAM HANLEY, PLS 1639. THE LOCATION OF THIS ORIGINAL CORNER RELATIVE TO THE BASIS OF SURVEY 74-81 WAS DETERMINED BY MEASUREMENT FROM TWO RECOVERED 1981 RANDOM SURVEY TRAVERSE POINTS LOCATED NEAR THE CORNER. POSITIONS FOR THE FOUR CORNERS TO BE REVISED AND FOR THE 1/4 CORNERS OF SECTIONS 9-10 AND 15-16 WERE CALCULATED USING THE APPROPRIATE SINGLE AND DOUBLE PROPORTIONATE MEASUREMENT PROCEDURES. A SEARCH FOR EVIDENCE OF THE G.L.O. SURVEY CORNER WAS MADE AT EACH CORNER POSITION MARKED "SFNF" NO EVIDENCE WAS FOUND.

THE REVISED CORNER POSITIONS INDICATED ON THIS DRAWING WERE DETERMINED BY CAREFUL MEASUREMENT WITH A STAFF COMPASS AND STEEL TAPE FROM THE EXISTING 1981 POSITION. THE STAFF COMPASS READINGS WERE COMPARED TO THE DIRECTIONS OF THE RECOVERED 1981 RANDOM SURVEY TRAVERSE AT SEVERAL LOCATIONS TO MAINTAIN THE COMPATIBILITY OF THE REVISED CORNER POSITIONS WITH THE 1981 SURVEY.

NEW CORNER ACCESSORIES WERE MARKED ONLY WHERE NECESSARY. THEREFORE, THE REMAINING 1981 CORNER ACCESSORIES (BEARING TREES) MAY NOT PRECISELY FACE THE REVISED CORNER POSITIONS.

UNION COUNTY SURVEYOR	
Date Received	9-18-89
Date Filed	9-18-89
By	G. LANGLITZ
File No.	15-89

REVISION TO SURVEY 74-81

LOCATED IN SECTIONS 9-10-15-16, T.2S., R. 40 E., WILLAMETTE MERIDIAN, UNION COUNTY, OREGON

FOR: ANDERSON-PERRY & ASSOC., INC. 101 FIR LAGRANDE, OR

SCALE: 1" = 1000'

DATE: SEPT. 1989

JOB NO. 823-40 DHE

SHEET NO. 1/1

anderson perry & associates, inc.
engineering • surveying • materials testing
LA GRANDE, OR. WALLA WALLA, WA. LEWISTON, ID.

