



Note: The centerline stations shown are record information.

### BASIS OF BEARING

Solar observations taken N 36°02'46" E  
9517.07 ft. from the Northeast corner of Section  
17 Township 1 South, Range 39 East of the  
Willamette Meridian.

NOTE:  
The bearings and distances shown are between the found monuments as they exist in the ground.

### LEGEND

- Found 5/8" iron pin ( smooth ).
- Found 5/8" iron pin ( rebar ).
- Found 5/8" iron pin with plastic cap marked BGA SURVEY MARKER. Survey no. 25-78
- ▲ Found PK nail.
- Computed position only no monument set.
- ( ) Record information
- [ ] Oregon State Highway grid bearing.

### NARRATIVE

This survey was ordered by Thomas G. Carman on behalf of the Oregon Department of Transportation. The state needed to purchase more right of way along this portion of highway 82 and needed this section of highway tied to a government corner for description purposes. There was little in the way of found corners in the immediate area of the road area. I tied the existing highway monuments as shown. None of the monuments are recorded with the exceptions of the found monuments on survey number 25-78. No monuments were set this survey.

The PI noted at the extreme South end of this survey was documented on survey number 25-78. I reestablished its position on paper from previous files, on survey number 25-78, to hubs and larks that were referenced ties to the PI. These hubs and larks are gone today as there has been some excavation activity in the area that these hubs were previously found. I find no other problems with this survey.

### REFERENCE MATERIAL

Oregon Department of Transportation Drawings  
2B-17-10  
8B-16-17  
  
Union County Survey 25-78  
  
Union County Remonumentation records

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Gregory T. Blackman*  
OREGON  
GREGORY T. BLACKMAN  
991

UNION COUNTY  
SURVEYOR  
11-22-89  
R. ROBINSON DEWITT  
11-28-89

<b>BAGETT - GRIFFITH &amp; ASSOCIATES</b> La Grande, Oregon Map of Survey A portion of the Rhinehart - Elgin Section of Highway 82. Located in sections 9 and 4 Township 1 South, Range 39 East of the Willamette Meridian. UNION COUNTY, OREGON		
SURVEYED FOR	Oregon Department of Transportation ( Thomas Carman )	
SURVEYED BY	GTB	11 - 89
Scale: 1" = 200'	Drawn by: JPP	11 - 89