



BASIS OF BEARING

Solar observation taken at a point 2856.26 feet South and 497.46 feet East of the Northwest corner of Section 3, Township 1 South, Range 39 East of the Willamette Meridian. (Same basis of bearing as survey number 28-89)

NARRATIVE

This survey was done at the request of Thomas G. Carman on behalf of the Oregon Department of Transportation. The state needed to purchase more right of way along this portion of Highway 82 and needed this section of highway tied to a government corner for description purposes. This survey is an extension of survey number 28-89, with both having the same basis of bearing. I monumented the Northwest corner of Section 3 from original GLO survey evidence. (See monumentation record filed separately). The monumented position agrees with the state plane coordinates shown on Oregon Department of Transportation drawing number 88-16-17. I tied the existing highway monuments as shown. The bearings and distances shown are to the found monuments as they exist on the ground. The centerline stations shown are record information from the Oregon Department of Transportation drawings. No new monuments were set on this survey other than the section corner. I find the existing PK nails along the centerline at stations 903+87.07, 908+00 and 909+00 not at or near the record distance from the found right of way monuments as shown. I find no other unusual conditions on this survey.

LEGEND

- Found 5/8" iron pin
- Found 1/2" iron pin
- ▲ Found PK nail
- ⊙ Set a 2 1/2" x 30" aluminum monument from original GLO survey evidence
- () Record information
- [] Oregon State Highway grid bearing

REFERENCE MATERIAL

- Oregon Dept. of Transportation drawing 28-17-10
- Oregon Dept. of Transportation drawing 88-16-17
- Union County Survey Number 28-89

REGISTERED PROFESSIONAL LAND SURVEYOR
Gregory T. Blackman
 GREGORY T. BLACKMAN
 921

UNION COUNTY SURVEY 3
 Surveyed 12-22-89
 12-27-89
 R. Robinson, Deputy
 File No. 31-89

BAGETT - GRIFFITH & ASSOCIATES LaGrande, Oregon MAP OF SURVEY A portion of the Rhinehart-Elgin section of Highway 82 Located in Section 3, Township 1 South, Range 39 East, and in Sections 27 and 34, Township 1 North, Range 39 East of the Willamette Meridian UNION COUNTY, OREGON		
SURVEYED FOR	Oregon Dept. of Transportation (Thomas Carman)	
SURVEYED BY	G.T.B.	12-89
Scale: 1" = 200'	Drawn by:	R.G.R. 12-89